


(LLOYDS REGISTER



VESSELS OF 100 TONS AND UPWARDS.

*** These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) ☒

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
104603		" Mount Sion		9 1895. Glasgow	
No., Date, and Port of Previous Registry (if any). Nil.					
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled	Where Built.	When Built.	Name and Address of Builders.	
British	Steamship. Screw.	Belfast	1895	Workman, Clark & Co. Ltd. Belfast.	

Number of Decks ...	Two	Length from fore part of stem, under the bowsprit to the aft side of the head of the stern post ...	335	Feet.	Tenths.
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	334	50	
Rigged ...	Schooner	Main breadth to outside of plate ...	43	70	
Stern ...	Round	Depth in hold from tonnage deck to ceiling at midships ...	26	10	
Build ...	Blended	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	-	-	
Galleries ...	None	Depth from top of beam amidships to top of keel ...	29	65	
Head ...	None	Depth from top of deck at side amidships to bottom of keel ...	28	90	
Framework and description of vessel ...	Steel	Round of beam ...	-	90	
Number of Bulkheads ...	Six	Length of engine room (if any) ...	43	75	
Number of water ballast tanks, and their capacity in tons ...	Five 452 tons				

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... } 6930 tons. Ditto per inch immersion at same depth ... } 29 1/4 tons.

PARTICULARS OF ENGINES (if any).

No. of Engines	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
One Set	Triple Expansion Surface Condensing Inverted cylinders Direct Acting Boilers.	British	1895	Workman, Clark & Co. Ltd. Belfast	Three 23" 37" 63"	42"	350 1850 10 1/2 knots
	Number ... Two						
	Iron or Steel ... Steel						
	Pressure when loaded 150 lbs						

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	3062.97	On account of space required for propelling power	1049.72
Closed-in spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	83.17
Space or spaces between Decks ...		These spaces are the following, viz.:—	
Poop ...	46.35	Deductions under S. 49 Act 1894.	
Forecastle ...	49.29	Captain's Cabin ... 16.13	
House on deck ...	42.06	" Bath ... 2.58	
Other closed-in spaces, if any, as follows:—		Chart Room ... 5.08	31.21
Excess of Hatchways	49.70	Boiler Store ... 17.42	
Spaces for Machinery &c } under S. 48 Act 1894		Cubic Metres.	
Gross Tonnage ...	3280.37	9283.45	
Deductions, as per Contra ...	1164.10	3294.40	
Registered Tonnage ...	2116.27	5989.05	
		Total Deductions ...	1164.10

Name of Master Edward Ellicott

Certificate of ~~Service~~ ☒ Competency No. 22625

No. of Owners Two

Name, Residence, and Description of Managing Owner if there are more owners than one.

John Smith & William Service both of 54 Gordon Street Glasgow are Managing owners.

Dated 19th March 1895.