

(LLOYDS REGISTER.)

LLOYD'S REGISTER OF SHIPING
RECEIVED G. 130
-4 NOV. 95
Lloyds.

65

VESSELS OF 100 TONS AND UPWARDS.

** These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) P.C.N.D.

Official Number.	Name of Ship.	No., Date, and Port of Registry.					
104,463.	Mounie.	11 1895.	Belfast.				
No., Date, and Port of Previous Registry (if any). ✓							
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled	Where Built.	When Built.	Name and Address of Builders.			
British.	Steam Screw.	Belfast.	1895.	Workman Black & Co. Ltd. Belfast.			
Number of Decks ...	Two.	Length from fore part of stem, under the bowsprit to the aft side of the head of the stern post ...	338	Feet.	Tenths.		
Number of Masts ...	Two.	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	337	6			
Rigged ...	Schooner.	Main breadth to outside of plank ^{plating} tank top at midships ...	43	7			
Stern ...	Round.	Depth in hold from tonnage deck to ceiling ^{ceiling at midships} ...	26	1			
Build ...	Blender.	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...					
Galleries ...	none.	Depth from top of beam, amidships to top of keel ...	29	8			
Head ...	none.	Depth from top of deck at side amidships to bottom of keel ...	29	1			
Framework and description of vessel ...	Steel.	Round of beam ...	56	9			
Number of Bulkheads ...	6	Length of engine room (if any) ...					
Number of water ballast tanks, and their capacity in tons ...	(aft tank 45, No. 2 140, No. 1, 265, 3, 290)						
PARTICULARS OF DISPLACEMENT.							
Total to quarter the depth from weather deck at side amidships to bottom of keel ...			6960 tons.	Ditto per inch immersion at same depth ... 29 tons.			
PARTICULARS OF ENGINES (if any).							
No. of Engines	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
One set.	Triple Expansion surface condensing Inverted Cylinders.	British.	1895.	Workman Black & Co. Ltd. Belfast.	Three 24" 40" 66"	45"	410 2050 12 Knots.
	Boilers: Three Keel 180 lbs		1895.	Do.			
PARTICULARS OF TONNAGE.							
GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.		
Under Tonnage Deck ...		3018.86	On account of space required for propelling power		1031.52		
Closed-in spaces above the Tonnage Deck, if any		—	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew				
Space or spaces between Decks ...		—	These spaces are the following, viz.:—				
Poop ...		—	Crew & Officers' Spaces		71.96		
Forecastle ...		30.33	Under Act '94, S. 79:—				
Round House ...		48.31	Master's Room 5.37				
Other closed-in spaces, if any, as follows:—			Chart Room 5.67		27.74		
Side Houses		30.74	Boatswain's Store 16.70				
Excess Hatchways		15.21	Total Deductions		131.22		
Spaces for machinery, Light & air, S. 78, Act, 1894.		80.50					
Gross Tonnage ...		3223.50	9122.50				
Deductions, as per Contra ...		1131.22	3201.35				
Registered Tonnage ...		2092.28	5921.15				
Name of Master		James Cullen.	Certificate of Service No. 018001.				
Name of Owners		one,					
Name, Residence, and Description of Managing Owner if there are more owners than one.		Daniel Dixon, Knight, 113, Corporation Street, Belfast. County Down.					
Dated		Belfast, 26th. October, 1895.					

BELLS-189