BEL66-0159 (1/2)

3 Decks. IRON OR STEEL STEAMER.

No. 4619

State if Report is also sent on the Machinery of the Vessel Yes

Date of completion of report 21st May 1896 *Port of* Belfast *Received at London Office* FRI. MAY 22 1896

Survey held at Belfast *Date, First Survey* 11th April 1895 *Last Survey* 20th May 1896

On the Steel Screw Steamer "Langton Grange" *Rig* Brigantine

THREE DECKED VESSEL.

CLASS + 100 A1 3 ak.

TONNAGE under Tonnage Deck	5447.93
Do. between Tonnage Dk. and 3rd and 4th Dk.	
Total under Upper Dk.	
Do. of Poop	
Do. of Bridge House	222.42
Do. of Forecastle	65.09
Do. of Houses on Dk.	40.59
Do. of excess of Hatchways above Crown of Engine Room	74.56
Gross Tonnage	5850.59
Less Crew Space	102.43
Less above Crown of Engine Room	74.56
Tonnage for Fees	5673.60
Engine Room	1872.19
Navigation Spaces	31.71
Under Tonnage	3844.26
Midship Beam	

	FEET.
Half Breadth *(moulded)*	26.95
Depth *from upper part of Keel to top of Upper Deck Beams*	33.63
Girth *of Half Midship Frame (as per Rule)*	56.50
	117.08
deduct 7 feet	7
1st Number	110.08
Length	417.5
2nd Number	459.58
Proportions—*Breadth to Length*	7.74
Depth to Length—Upper Deck to top of Keel	12.41
Main Deck ditto	15.97

Master C. S. Crichton

Year of appointment (1) *As Master in service of owner of present vessel* 18 (2) *As Master of this vessel* 18

Built at Belfast

When built 1896 *Launched* 29th July 1896

By whom built Workman Clark & Co. Ltd.

Owners Houlder Bros & Co

Managers (Where necessary to be entered in Reg. Book.)

Residence 146 Leadenhall Street

Port belonging to London. E.C.

Destined Voyage Brisbane *If Surveyed while Building, Afloat, or in Dry Dock* Building

	Feet.	Inches.		Feet.	Inches.		Feet.	Inches.		Horse.	
LENGTH on Deck / Rule	417	6	**BREADTH**— Moulded	53	10¾	**DEPTH** top of Floors to Upper Deck Beams / Do. do. Main Deck Beams	29 / 21	7 / 3½	Power of Engines	650	No. of Decks with flat laid: Two; No. of Tiers of Beams: Two

Dimensions of Ship per Register, Length 420.0 breadth 54.2 depth 29.55 Moulded depth, ft. 32 ins. 5 To Upper Dk. Round up of Beam, Upper Dk. 14½ ins.

FRAMING.

	Inches in Ship.	Inches in Ship.	16ths or 20ths in Ship.	Inches per Rule Or as	Inches per Rule Approved	16ths or 20ths per Rule ved.
KEEP, Angles, ~~or L, E or [Bars~~ for ¾ length amidships	7	3½	11	7	3½	11
,, For ¼ at each end			10			10
Plate in way of Double Bottoms at Solid Floors	3½	3½	10.69	3½	3½	10.69
,, ,, at intermdt. Bkts.	alt	Solid floors				
Distance of Frames from moulding edge to moulding edge, all fore and aft	26			26		
REVERSED FRAME, Angles	7	3½	11.10	7	3½	11.10
DEEP FRAMING, depth of girder	10½			10½		
FLOORS, depth and thickness of Floor Plate at mid-line for ¾ length amidships						
,, in way of Engines and Boilers						
,, thickness at the ends of vessel						
,, depth at ¾ the half breadth, as per Rule						
,, height extended at the Bilges						
BRACKETS in **Cell Dble Bottoms**			9.8			9.8
,, Distance apart	26			26		
CENTRE GIRDER, in Double bottom, depth and thickness	48		11.69	48		11.69
,, Angles, Top	4	4	10.69	4	4	10.69
,, ,, Bottom	6½	4½	10.69	6½	4	10.69
SIDE GIRDERS, number and thickness two each side			9.8			9.8
,, Angles	3½	3½	10.69	3½	3½	10.69
MARGIN PLATE, depth (exclusive of flange) and thickness	36		10	36		10
,, Angles	4	4	10	4	4	10
OUTER BOTTOM PLATING, breadth and thickness of **Middle Line Strake**	52		11.69	52		11.69
,, ,, in Engine and Boiler space			8/16			8/16
,, ,, Remainder in Holds			9.8			9.8
BEAMS, Upper Deck, ~~Single Angle~~, ~~Bulb~~ Angle, ~~Plate or~~ Tee Bulb	11		11	11		11
Angles on upper edge						
Average space	52			52		
BEAMS, Middle Deck, ~~Single Angle~~, Bulb Angle, ~~Plate~~ or Tee Bulb	12 / 9	3½	12 / 13	12 / 9	3½	12 / 13
Angles on upper edge						
Average space	52 / 26			52 / 26		
BEAMS, Lower Deck, Single Angle, Bulb Angle, Plate or Tee Bulb						
Angles on upper edge						
Average space						
BEAMS, Hold, or Orlop, Plate or Tee Bulb						
Angles on upper edge						
Average space						
BEAMS, Poop Deck, ~~Angle~~, ~~Bulb Angle~~, ~~Plate~~ or Tee Bulb	10		10	10		10
Angles on upper edge						
Average space	52			52		
BEAMS, Bridge Deck, ~~Angle~~, ~~Bulb Angle~~, ~~Plate~~ or Tee Bulb	10		10	10		10
Angles on upper edge						
Average space	52			52		
BEAMS, Forecastle Deck, ~~Angle~~, ~~Bulb Angle~~, ~~Plate~~ or Tee Bulb	10		11	10		11
Angles on upper edge						
Average space	52			52		
PILLARS, In 'tween Deck, size and spacing	3	52		3	52	
,, ,, **Hold** ,, ,,	4⅜	52		4⅜	52	
,, ~~Quarter 'tween Dks.~~, ~~in Hold~~ ,, ,,	Two pillars to each beam					
WEB-FRAMES in Fore Body, No. and spacing						
,, ,, brdth. & thickness						
,, No. Side Stringers ,, ,,						
WEB-FRAMES in E. & B. Space, No. & spacing	Three 13 ft			Three 13 ft		
,, ,, brdth. & thickness	20		11	20		11
WEB-FRAMES, In After Body, No. and spacing						
,, ,, ,, brdth. & thickness						
,, No. of Side Stringers ,, ,,	Four			Four		
,, Size of Angles or Tee Bars to **Web-Frames**	4½	4	10	4½	4	10
BRACKET PLATES to Stringers between Web Frames, depth and thickness						

FORGINGS or CASTINGS.

	Inches in Ship.	Inches per Rule. Or as Approved.
KEEL, Bar or Side Plates, depth and thickness	Flat plate Keel	
STEM, moulding and thickness	12 × 3⅛	12 × 3⅛
STERN-POST for Rudder do. do.	12 × 7¾	12 × 7¾
,, for Propeller	12 × 7¾	12 × 7¾
MAIN PIECE of **Rudder,** diameter at head	10½	10½
,, ,, do. at heel	5½	5½
RUDDER, how constructed	Single plate 22/20	
Can the Rudder be unshipped afloat?	Yes	

KEELSONS & STRINGERS.

	Inches in Ship.	Inches in Ship.	16ths or 20ths in Ship.	Inches per Rule Or as	Inches per Rule Approved	16ths or 20ths per Rule ved.
CENTRE LINE KEELSON, Vertical Plate above floors, Through Plate, or Intercostal Plate						
,, Rider Plate						
,, Bulb Plate to Intercostal Keelson						
,, Horizontal Plates on Floors						
,, Angles						
SIDE KEELSON, Angles						
,, Bulb or Plate above floors, for lng.						
,, Intercostal Plate, for length						
,, Attached to outside Plating with Angle						
BILGE KEELSON, Angles						
,, Bulb or Plate above floors, for lng.						
,, Intercostal Plate for length						
Four ,, Attached to outside Plating with Angle						
~~**BILGE**~~ **STRINGER** ~~Angles~~	9 × 3½ × 12.10/20					
,, Bulb Plate for length						
,, Intercostal Plate ~~for~~ 12.10/20 for ~~whole~~ length	10/20					
,, Attached to outside Plating with Angle	4 × 4 × 10/20					
SIDE STRINGER Angles	4½ × 4 × 10/20					
,, Bulb or Intercostal Plate, for lng.						
,, Attached to outside plating with Angle						



Upper Deck Stringer Plates, br'dth & thickness	65 & 50	1369	65 & 50	1369		
,, Angle on ditto	5 × 5	11.10	5 & 5	11.10		
,, Tie Plates fore and aft, outside Hatchways						
,, Deck.* ~~Iron or~~ Steel, for whole lng.		9.8		9.8		
,, Wood Deck. Material & thickness						
Middle Deck Stringer Plate, br'dth & thickness	65 & 50	11.69	65 & 50	11.69		
,, Angles on ditto, No. Two	4 × 4	9.8	4 × 4	9.8		
,, Tie Plates outside Hatchways						
,, Diagonal Tie Plates on Bms., No. of prs.						
,, Deck.* ~~Iron or~~ Steel, for whole lng.		8.4		8.4		
,, Wood Deck. Material & thickness						
Lower Deck Stringer Plate, br'dth & thickness						
,, Angles on ditto, No.						
,, Tie Plates, outside Hatchways						
,, Deck.* Material and thickness						
Hold, or Orlop Stringer Plate, br'dth & thckn's						
,, Angles on ditto, No.						
,, Tie Plates outside Hatchways						
,, Deck. Material and thickness						
Poop Deck Stringer Plate, breadth & thickness	41	8	3.5	8		
,, Angle on ditto	4 × 3½	8	4 × 3½	8		
,, Tie Plates	16	8	15	8		
,, Deck. Material and thickness	3" Y.P.		3" Y.P.			
Bridge Deck Stringer Plate, br'dth & thickness	54	10	54	10		
,, Angle on ditto	4 × 3½	10	4 × 3½	10		
,, Tie Plates	20	9	20	9		
,, Deck. Material and thickness	3" Y.P.		3" Y.P.			
Forecastle Deck Stringer Plate, b'dth & th'kns	48"	8	35	8		
,, Angle on ditto	4 × 3½	8	4 × 3½	8		
,, Tie Plates	16	8	15	8		
,, Deck. Material and thickness	3 Y P		3 Y P			

* *If Iron or Steel Deck, state if whole or part, and if Wood Deck is laid thereon.*

BULKHEADS.

	Number. In Vessel.	Number. Per Rule.	Thickness. 16ths or 20ths.	STIFFENERS. Horizontal. Inches.	Vertical. Inches.	Spacing Inches.	Single or Double Frames.	Height up.
W. T. BULKHEADS	4	6	8.4	9 × 3½ × 13/20	6½ × 3½ × 10.69	48 30	Double	Up all
PARTITION ,,	1		6	10 × 3½ × 9/20	Flanged	36"	Single	Middle
LONGITUDINAL ,,				Not fitted				

Are the outside Plates doubled two spaces of Frames in length? Yes

Form No. 1B.

BEL66-0159 (2)2

PLATING.

STRAKES.	AS IN SHIP. AMIDSHIP. Breadth.	AS IN SHIP. AMIDSHIP. Thickness.	AS IN SHIP. FORWARD. Thickness.	AS IN SHIP. AFT. Thickness.	PER RULE OR AS APPROVED. AMIDSHIP. Breadth.	PER RULE OR AS APPROVED. AMIDSHIP. Thickness.
	Inches.	~~16ths or 20ths~~	~~16ths or 20ths~~	~~16ths or 20ths~~	Inches.	~~16ths or 20ths~~
Flat Plate Keel (If Bar Keel, state Riveting)	36	18	14	14	36	18
Garboard or A Strake		14	13	13		14
B "		12	10	10		12
C "		12	10	10		12
D "		12	10	10		12
E "		14	11	11		14
F "		14	11	11		14
G "		14	11	11		14
H "		13	10	10		13
J "		13	10	10		13
K "		13	10	10		13
L "		13	10	10		13
M "		13	10	10		13
N "		13	10	10		13
O "		17	10	10		17
Keel — (P) "	50	19	12	12		19
Q "						
R "						
Doubling of Flat Plate Keel	½	14			½	12
Length and thickness of Bilges						
Length and thickness of Sheerstrakes						
Length and thickness of Strake below						
Poop Sides				7		7
Bridge Sides		10	9			10
Fore-castle Sides			7			7

RIVETING.

EDGES. Single or Double.	EDGES. Breadth of Lap.	EDGES. Rivets. Diam.	EDGES. Rivets. Spacing cr. to cr.	BUTTS. Double or Treble and for what Length.	BUTTS. Rivets. Diam.	BUTTS. Rivets. Spacing cr. to cr.	BUTTS. Straps. Breadth.	BUTTS. Straps. Thickness.	BUTTS. If Lapped. Breadth.	BUTTS. If Lapped. For what Length.
	Inches.	Inches.	Inches.		Inches.	Inches.	Inches.	Inches.	Inches.	Feet.
Double	6	1	4⅓	Treble	1	3½	10½	21/20		
"	5¼	1	3 7/4	"	"	"			10½	to 9
"	"	⅞	"	"	⅞	3⅜			9	whole
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	"	"	"	"	"	"			"	"
"	6	1	4⅓	"	1	3½	10½	14/20 outside 9/20 middle		
"	6	1⅛	"	"	1⅛	4	21½	15/20 outside 9/20 middle		
Single	2½	¾	3½	Double	¾	2 7/8			5	
Double	4½	"	"	Treble	⅞	3 1/16			8½	
				Double	¾	2 7/8				
Single	2½	"	"	Double	¾	2 7/8			5	

Manufacturer's name or trade mark of the Iron or Steel (state process of manufacture of Steel) used for Frames, Floors, Beams, Keelsons, Tie and Stringer Plates, Plating, &c.? Thos. Y ors forms:- Colvilles Y Steel Co. Brns:- Dorman Long Y Steel Co. Stringer pls:- Stockton, Barrow Y Bolckow Vaughan. Stringer Y bhd angles:- Dalzell, Hallside Y Lanarkshire. Floors:- Clydebridge Y Barrow. Dks:- Barrow. Bhd plates:- Hill Co, Y Barrow Steel:- Stockton. Ballast tanks:- Stockton, Bolckow Vaughan Y Hill Co Marti:- Bolckow Vaughan. Lids Stringer plate:- Stockton Steel Co

Upper Deck Stringer Plate {**Butts,** treble riveted for whole length amidship. **Straps,** ~~single~~, double ~~or overlapped~~ for half length amidship.
Middle Deck Stringer Plate {**Butts,** treble riveted for whole length amidship. **Straps,** ~~single, double~~ or overlapped for whole length amidship.
Butts of Bilge & Side Stringers and Tie Plates, treble or double riveted? Trebles
Inner Bottom Plating, riveting of **Edges** Doub. Y Sing. **Butts** Double
Centre Girder Butts, Treble riveted **Keelson Butts,** " " riveted.
Frames, riveted through Plates with 1" Y 7/8" in. Rivets, about 7" Y 6½ apart.
Rivets, state whether Iron or Steel Iron.

FRAMES extend in one length from margin plate to upper deck, Y all carried up in Bridge Poop Y Forecastle
REVERSED FRAMES on floors and frames extend from margin plate to main Y upper decks alternately. All to upper deck abaft after peak bulkhead Y Alternately to forecastle deck.

MASTS, SPARS, &c.

	Material.	Total Length.	Diameter and Thickness. At Partners.	Heel.	Hounds.	Head.	No. of Plates in round.	Angles. Number.	Angles. Size.	Riveting. Seams.	Riveting. Butts.
Lower Masts. Fore	Steel	53'-3"	24 x 9/20	24 x 9/20	21 x 7/20	8 x 7/16	Two			Single	Treble
Main	"	56'-0"	24 x 7/20	24 x 7/20	18¼ x 6/20	topmast	Two			"	"
Mizen											

Bowsprit

Topmasts, Yards and Remainder of **Spars** Steel fore topmast Y lower yard. Main topmast Y other yards pine.
Rigging, Material and Size, **Shrouds** Fore Shrouds 4" (4 a side) Main 3¾ (4 a side) **Stays** Fore 4½" (double) Main 4½ (single)
Sails. One Suit of best Canvas by Sails, and the following spare sails
Duncan Gray Y Sons, Glasgow.

EQUIPMENT No. 53376 LETTER a f. ANCHORS.

Number of Certificate.	Anchors.	Weight, Ex. Stock. Cwts.	qrs.	lbs.	Weight of Stock. Cwts.	qrs.	lbs.	Test, per Certificate. Tons.	cwts.	qrs.	lbs.	Weight Req. by Rule. Cwts.	qrs.	lbs.	Description of Anchor.	Makers.	Where and when tested and Superintendent.
28325	1st Bower	58	1	0	Stockless			47	7	2	0	58	0	0	Lion patent 136	Jno Abbott & Co	Sunderland 23/9/95 J.H.
28270	2nd "	58	1	0	"			47	7	2	0	58	0	0	" " 133	" " "	" 7/9/95 "
28365	3rd "	56	2	0	"			46	6	1	0	56	2	0	" " 135	" " "	" 20/9/95 "
28367	Spare Bower	52	0	0	"			43	12	2	0	51	1	0	" " 134	" " "	" 20/9/95 "
Collection	Stream weight	225	0	0								223	3	0			
13518	Kedge Stream	16	3	0	4	2	0	18	0	2	14	16	3	0	Rodgers Patent	" " "	Low Walker 29/3/93 C.E.P.
14502	2nd Kedge	8	2	14	2	1	0	10	15	0	0	8	2	0	" "	" " "	" 30/3/95 "

If Patent state name of Patentee.

CHAIN CABLES.

Number of Certificate.	Fathoms.	Size.	Test per Certificate. Tons.	Weight of Chain Cable. Supplied.	Weight of Chain Cable. Per Rule.	Fathoms and Size per Rule.	Description.	Makers of Cables.	When and where tested, and Superintendent.
4164	135	2 7/16	96¼	36 2 1 11	17 2 0 3 4	240 fms 2 7/16 dia	Stud	Jno Abbott & Co	Low Walker 25/4/93 C.E.P.
4170	135	2 7/16	96¼	36 2 0 20		2 7/16 dia	Stud	" "	" "
Towline				724-2-13					
Iron Stream Chain or Steel Wire	120	5¼	71			120 fms 5¼	S. W.	W B Brown & Co. Rawhall & Ross	
Stream Wire	90	5"	39			90 fms 5"	S. W.	" " "	

HAWSERS AND WARPS.

Material.	Fathoms.	Size.	Breaking Test of Steel Wire Towline.	Fathoms and Size Per Rule.
Towline S. W.	90	4	33	90 fms 4"
Hawser S. W.	90	3½	22	90 - 3½
Warp	180	6½		
	90	4½		
	90	4		

Boats Two lifeboats 26'-0" x 7'-9" x 3'-7" Carter 26'-0" x 6'-0" x 2'-7" Dingy 20'-0" x 6'-0" x 2'-7"
Pumps, Number Ten manual pumps Diameter of Barrel and Tail Pipe 5" barrels 2½" tail pipes. Aft well 6" bar 3"
Windlass is by Emerson, Walker Y Thompson Bros Ltd Y **Capstan** Combined
Engine Room Skylights.—How constructed? Plates Y angles.
What arrangements for deadlights in bad weather? Bull's eyes in iron frames.
Coal Bunker Openings.—How constructed? Plates Y angles How are lids secured? 3" hatches Height above deck? 10" under Bridge
Number of **Scuppers,** and numbers and dimensions of **Freeing Ports, &c.** Six scuppers a side. Eight freeing ports a side 2'-9" x 1'-0"
Ceiling in Holds, thickness and material 2½ pine **Ceiling 'tween Decks,** thickness and material 2½ pine
Cargo Hatchways.—How formed? Plate Y angles **Hatches,** If strong and efficient? Yes
State size **No. 1 Hatch** (Forward) 21'-8" x 14'-0" **No. 2 Hatch** 21'-8" x 14'-0" **No. 3 Hatch** 21'-8" x 14'-0" **No. 4 Hatch** 21'-8" x 14'-0"
Number of **Web Plates, Shifting Beams** and **Fore** and **Afters** to each Hatch Three fore Y afters Y one deep web to each hatch
No. of Breasthooks Four **No. of Crutches** Deep floors
Bulwarks, height above deck and description 4'-9" of 4/16 plates **Main Rail,** material and size Iron. Patent section 6" x 3"

The above is a correct description. WORKMAN, CLARK & CO., LIMITED. SECRETARY
Builder's Signature (here only)

Surveyor's Signature A. L. Jones
Surveyor to Lloyd's Register of British and Foreign Shipping.

Form No. 1B.

Correspondence.—State dates and initials of letters respecting this case (*Reference should be made to any correspondence connected with this case*) M. Marcus 11 to 2
April 26. May 3. 9. 12. June 10. July 3. Aug 8. 29. (1895)

Workmanship. Are the butts of plating planed or otherwise fitted? Planed
Is the riveted work properly closed? Yes
Are the liners between the frames and plates solid single pieces? Yes Do the holes for riveting plate to frames, butt straps, or plate to plate, &c., conform well to each other? Yes Are the rivet holes well and sufficiently countersunk in the plate and punched from the faying surfaces? Yes Do any rivets break into or through the seams or butts of plating? No.
Are the butts of Plating, Stringers, &c., properly shifted and strapped? Yes

General Remarks (State quality of workmanship, &c.) This vessel has been built in accordance with the approved plans Y the Secretary's letters of the above dates. The workmanship is good throughout.
The weather deck has been tested for watertightness as required. The hand pumps Y watertight doors have been tested Y found satisfactory.
Nos 1. 2. Y 4 holds have been insulated for refrigerating purposes.
The following tracings accompany this report 'Midship section' (already forwarded) 'Profile' 'Deck plating' 'Pillars' 'Rail Plan' 'Masts' 'Portable Stanchions' 'Hatchways' 'Stern Y Rudder frames' 'Bracket connections of side stringers'; also Centreplates for the stern frame, rudder frame Y stern frame Y casting.

The Surveyor should state the Number of Report and Name of any Sister Vessel.

PARTICULARS FOR RECORD in the REGISTER BOOK.—Length of Poop 33'-5 ft., R.Q.D. or Break - ft., Bridge Dk. 197-2 ft., F'castle 77-7 ft. (in feet and tenths). When the Poop is joined to the B.D., this should be distinctly stated

No. and Material of Decks (if Iron or Steel) and whether wholly or partially covered with wood, and No. of tiers of Beams (this information is to be given as it should appear in the Register Book) Two decks, steel. Two tiers of beams Y deep framing
Official No. ; Signal Letters
How are the surfaces preserved from oxidation? Inside Cement Y paint Outside Paint.

PARTICULARS OF WATER BALLAST.—State whether the Double bottom is constructed on the cellular system Yes.

Where fitted.	Length. Feet.	Water Capacity. Tons.	Where fitted.	Length. Feet.	Water Capacity. Tons.
Double bottom, aft, No 4 tank	114-8	365	Fore peak tank,		150
Double bottom, forward, Nos 1 Y 2 tanks	149-6	550	After peak tank,		80
Double bottom, under Engines and Boilers, No 3 tank (Ballast tanks)	71-5	300	Midship deep tank,		
Double bottom, if under Engines only,			Other tanks, if fitted,		
Double bottom, if under Boilers only,		12	(If necessary, furnish further information by sketch.)		

State whether the above have been tested as required by the Rules. All tanks tested.

Order for Special Survey No. 396 Date 22nd Mar. 1895
Order for Ordinary Survey No. Date
No. 124 in builder's yard.

Dates of Surveys held while building as per Section 18.

1st. On the several parts of the frame when in place, and before the plating was wrought: April 11. May 7. 30. June 17. July 8. 22. 24. 29.
2nd. On the plating during the process of riveting: Aug. 9. 12. 15. 22. 29. Sept 4. 11. 18. 23. 26. 30 Oct. 14
3rd. When the beams were in and fastened, and before the decks were laid: Nov. 13. 15. 19. 25. Dec 3. Jany. 8. 22. 29. Feby 3. 5. 20. 26.
4th. When the ship was complete, and before the plating was finally coated or cemented: March 16. Apr. 3 & 5. 16. 17. 22. 24.
5th. After the ship was launched and equipped: May 5. 7. 1896.
Total No. of Visits 44

The amount of Entry Fee £ 5 : 0 : 0
Special Survey Fee £ 166 : 16 : 6
Travelling Expenses, if any £ : :

Fees applied for, 20th May 1896
Received by me, 22. 5. 1896

Certificate to be sent to Belfast Office

I am of opinion this Vessel should be Classed + 100 A1. 2 Dks (Stl) deep framing
With, or without Freeboard, as condition of Class Without

A. L. Jones
Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute TUES. MAY 26 1896
Character assigned 100 A1 Steel 2 Dks (Stl.) + deep framing
Large + Lmc 5 96 1 7.D.

The Surveyors are requested not to write on or below the Committee's Minute.

Hull Certificate, Written.

© 2019 Lloyd's Register Foundation