

Li: S Rgn:
15.12.83.

Iron Works. S. S. No 7.

Fore Mast
Length extreme 68'-6"

Effizienz
6/12. 83

11/2 84
 Laxness

Scala $\frac{1}{2}'' = 1 \text{ Fod.}$

Remarks.

Seams of Plating to be double rivetted.
Straps $\frac{1}{16}$ thicker than Plates, double
rivetted below Partners, remainder treble rivetted.
Rivets 5 diameters apart in edges.

14/12/83

Mart. Olsen & Co.
Ap. 12/ Laxevaag.
BERGEN.