

Mr. Hapledon of Bushy Ice of Feb. 1877
 100 fms. length 67 1/2 ft. Breadth 20 ft. Depth
 8 1/2 ft. intended to close 9 years P. Oak
 2 rows of metal fastenings 1 row of metal
 1st cutting of 10 years.

E. Oak - 12 yrs.
 The frame, beams, planks, and
 five upper strakes of English Oak.
 Holton, Pitch Pine, hog English Oak,
 flat of bottom outside English Elm and
 Beech, remainder of the plank Pitch Pine.

Metal fastened to entice two years
 and thoroughly salted. Steel
 stem and stem post 9 in. Holton.
 10 x 17 hog 8 in. Floor 9 x 8 1st 7 1/2 in.
 E.O. 12 yrs 2nd 7 3rd 6 1/2. Staircase 3 in. frames

8 x 10 3 1/2. Barges outside 4 in. Barges inside 3 1/2
 other plank from. Hull to masts 2 1/2 in.
 17 x 10 Ceiling 2 1/4 - P.P. (9 yrs) 3 1/4
 2 1/4 English Oak (12 yrs)

2 1/4 H. Poplar
 12 in.

30/3/77.

E.O. 12 yrs
 Oak - 30 years

12 yrs
 3
 3 1/2
 E. Oak
 (12 yrs)

P. Pine 12 yrs

1 1/2

4" 20/7/77

30/4/77

Lloyd's Register
 Foundation

BID75-0267.