

From
William Westcott Shipbuilder, Barnstaple — Schooner, Length
70 feet, Breadth 19, Depth 7 ft 10 in about 70 tons, to be
specially surveyed to class A. 12 Years — The Frame, Beam,
Keelson and three upper sheaths outside of be of English Oak, Bilges
outside and flat of Bottom English Elm, remainder of Plank
Pitch Pine, Shelves 7 x 10 x 3 1/2, Two pair of long iron Kiders taking
Plank sheer
English Oak

two bolts in the floor and an iron knee to every
Beam, Keel Elm 10 x 13 Keelson 10 x 1, Floor 8 in
"Tuttocks 7" 2nd do. 6 1/2 3rd do. 6 in, Shear
strake Water 3 1/2, Water to Bilge 2 1/2 Bilge 3 1/2,
Flat of Bottom 2 1/2, Ceiling 2 in, Limber Sheath 3 in
To be thoroughly sanded according to Rules.

Barnstaple 29th May 1882.

2.6.82



Mary Agnes
No 1994

10 yrs Table A
1 yr mixed material
1 yr Salt & if in accordance
with the Rules.



Lloyd's Register
Foundation

BIDTS-0353