

ed by Chief Surveyor 20.12.97

Received from Chief Surveyor

'S NAME Wood Bk. "William Gordon" Report Apl. No. 2608

he remarks of the Chief Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Survey

First Entry

This Wood Barque was built at Buctouche N.B in 1876 of 8 to 12 years material, with scantlings in excess of the Rules, and has not hitherto been classed in this Society's Register.

She has now been placed in dry dock and opened up for examination. The requirements of the Rules for the 2nd Survey for A in Red, sec.60, and the requirements of sec.52 for ships not built under survey, have been complied with, and the following repairs done:—

All the sheathing stripped off, vessel recaulked from keel to covering board, middle line rebolted in accordance with the Rules, bottom remetalled on felt, a portion of the main keelson renewed, new sister keelsons fitted, the fore mast step, partners and wedges, the bolsters and cross trees to the main mast and two yards renewed, rudder braces bushed and refastened, a new main hatch beam, and a new iron breasthook with pointers fitted, and various minor repairs.

The vessel is reported to be now in good and efficient condition, and it is submitted she appears worthy of the favourable consideration of the Committee to be classed A in Red for 5 years from December, 1897, being two-thirds of the number of years to which she would have been entitled originally (namely 8 years), with record of survey 12.97 and notation of F&YM.11.97.

A —
12.97
S. S. Apl. 97 — 5 yrs.
F&YM 11.97

1 DR 2 1/2 B. 15 1 B.
Moulded depth 21' 0"



© 2019

Lloyd's Register
Foundation

P.T.O.

22 DEC. 1897
Also for J.M. Hill to note.
B is requested

BID 77-0172