

op 4
Barrow in Furness 4th Dec 1894

Dear Sirs,

The new steamer "Claw Mackay" has left this port for Glasgow and to complete the survey the safety valves require to be adjusted and tested, working pressure 200 lbs \square "

Before her departure the safety valves were adjusted but on trying the valves for accumulation under forced draught, the increase of pressure was found to be excessive viz 25 lbs with the fan running at a moderate speed.

As there was no time to make any alteration to the valves before the vessel's departure for Glasgow, it was arranged with the Builders to have this done on her arrival.

Will you therefore give this case the necessary attention and report to London in due course

Yours faithfully
(Sd) Jas. Bathope

The Surveyors
Glasgow.



© 2020

Lloyd's Register
Foundation

BRW44-0026