

Schooner "Rheidol" 107 Tons, built
under Special Survey at Aberystwith, and
recommended for the 12 A-1 class.

Dimensions, 88 x 21-6 x 10-9

Proportions, over 8 depths to length:

This vessel requires, by the Rules, diagonal
plates on the frame, As compensation
the whole of the inside and outside =
planking is thicker than required by the
Rules and four pairs of long iron rider
knees are fitted extending over the floor
heads, and the fastenings are additional.

The vessel has been built in other
respects in accordance with the approved
Sketch of Midship Section appended.

It is respectfully submitted in view
of the larger scantlings and additional fastenings
of this vessel, she appears worthy of
the favorable consideration of the Committee
to be classed 12 A-1.

9 x 12 2/3" matl.

Salted

cf.

J. H. J.

11/4/78.



© 2021

Lloyd's Register
Foundation