


White Lion Court Cornhill

1<sup>th</sup> November 1834.

Dumfries.

In looking over the Report of the Steam  
Hepet "Grand Turk" received from the Glasgow Surveyor.  
I perceive that part of her Floor Timbers are reported to  
be of Elm, which by the Rule reduces her to the  
Class 5A1. From the manner in which the Frame  
is enclosed. I could only obtain a limited view of  
the Floor - which in that part were of Oak, and the  
Carpenter, who worked upon her whilst building, said  
that the whole Frame was British Oak, as I have  
stated in my Report - The Addition Sleepers referred  
to in the Clyde Survey are probably under the Boilers  
as usual & could therefore not be seen by me.

The Glasgow Report of the Diagonal Trussing  
is so worded as to convey the idea that the Ceiling is  
plaid diagonally - The Ceiling is of Fir worked in



Lloyd's Register  
Foundation



longitudinal staves - and upon the Ceiling  
diagonal pieces of American Oak are worked so  
as to give the appearance of being diagonally  
trussed with Oak -

In my opinion having Elm in her floor  
she should not be classed more than 5A1  
instead of 7A1 as recommended by my former  
report

I am Sir

Your Obedient Servant  
George Bayley

C Graham Esq

Wm Lloyd Garrison  
2nd Nov 1889

CLY89/19 1/2



© 2021

Lloyd's Register  
Foundation



*Chatham Esq*



© 2021

Lloyd's Register  
Foundation