

New July 25

Ans July 26

Wood vessel to be built by Messrs
Harg Brothers to class 12 A

Tracing of midship section and
Preliminary Report forwarded by
Mr. Lodrig.

Dimensions 140 ft x 27.0 ft x 13.6 ft in
Proportions 10.3 depths in length.

Provided diagonal plates be
let into the outside of the Frames as
required by section 39; Six upper
strakes of outside planking be not less
than $4\frac{3}{4}$ thick - tapering from thence into
the thickness of the bottom planking; the
Rules section 46 be fully complied
with, and all through bolts be clenched
on the outside planking, as shown in
the sketch; the Rules in all other respects
be complied with to the satisfaction of
the local Surveyor, and the vessel
be properly salted in accordance with
the requirements of Section 37, this
vessel will, it is considered be eligible
to be classed as follows, viz.

9 years under Table A

1 - for yellow metal fastenings
1 - for Sailing.

T/A

Should the vessel be built under
an efficient Roof, and the Rules Section
48 be complied with, she will on a fa-
vorable report be eligible to be classed
12A.

18th

26/7/23

© 2021

Lloyd's Register
Foundation