


Recd

134 "Panda"  am 5/3

It would appear from the Report, that all the bolts in the throats and arms of the Transoms and Hooks are of Iron. All the bolts in the Hold beam knees also appear to be of iron.

It should ~~be~~ submitted be distinctly stated whether the bolts in the side arms of the Hold beam hanging knees are of yellow metal driven through and clenched on the outside planking, ^{"in knees, bolts of planking &c."} also whether all the "through bolts" are of yellow metal from the lower side of the keel up to the height of one fifth the midship depth of Hold, set down below the upper side of the deck at the side, and parallel thereto forward and aft, or to the height shown on the drawing returned.

 W. W. 5/3/25



© 2021

Lloyd's Register
Foundation