

Her Masts, Yards, &c. are in Good condition, and sufficient in size and length.

She has SAILS.		CABLES, &c.		ANCHORS, and their weights.	
N ^o .			Fathoms. Inches.		N ^o . Weight.
/	Fore Sails,	Chain	90 1	Bower,	2 8.1.20
/	Fore Top Sails,	Hemp Stream Cable	90 1/2		8.1.20
2	Fore Topmast Stay Sails,	Hawser	50 7/16	Stream,	1 2.3.20
/	Main Sails, <i>Lyspail</i>	Towlines	75 7		
/	Main Top Sails,	Warp	73 6 3/4	Kedge,	1 1.3.5
	and <i>other sails req</i>	All of <u>Good</u> quality.	73 5		
			73 4 1/2		

Her Standing and Running Rigging Mu & Hump sufficient in size and _____ in quality.

She has One 16 1/2 ft Long Boat and _____

The present state of the Windlass is Good ~~Capstan~~ Good Rudder Good Pumps 2 Metal

General Remarks and Statement and Date of Repairs, if any.

DATES of Surveys held while building, as per Section 35.

1st. When the Frame is completed 23 & 30 January

2nd. When the Beams are put in, &c. 30 April

3rd. { When completed, and before the } 28 May
 { plank be painted or payed }

This is a vessel of fair materials for the class designed is square sterned formed without transoms the stem & Counter timbers filling in against after Cant timbers, planking will run out in this & otherwise secured with Hooks Beams &c

Has a raised Quarter deck about 19 inches high & 17 1/2 ft in length from front of Break to after part - stern post on deck - has no overlap at Break

Present condition of Caulking of Bottom, Good Deck, Trim and Waterways Trim

If Sheathed, Doubled, Felted, or Coppered Single Bottom When last done _____

I am of opinion this Vessel should be Classed 7 A1

The Amount of the Fee.....£ 2 : - : - is received by me, Thomas Alexander

Special£ 3 : 3 : -

Certificate£ 2 : 6 : - requested to be forwarded direct to Bureau

Committee's Minute 5 July 1864

Character assigned A 1 for 7 Years



© 2019

Lloyd's Register Foundation