

Б. ОУТ С. С N°146

NOTE.

SEAMS $2\frac{1}{4}$ " BROAD AND SINGLE RIVETTED
THROUGHOUT; $\frac{5}{8}$ " RIVETS, SPACED $3\frac{1}{2}$ " CENTRE TO CENTRE
BUTTS, BELOW DECK, DOUBLE RIVETTED WITH STRAPS
 $\frac{1}{20}$ " THICKER THAN THE PLATES THEY CONNECT
ABOVE DECK, TREBLE RIVETTED, WITH STRAPS
 $\frac{2}{20}$ " THICKER THAN THE PLATES THEY CONNECT.
BUTTSTRAPS FITTED INSIDE

Steel Tole
Mast
of
S. S. No. 146.
—
Gourlay Bros. & Co.
—
S. S. "Farmigan".
—
Dundee.
Report No. 5469.

DUN116-0264



© 2019

Lloyd's Register
Foundation