

New wood schooner "Julia" of 169 Tons
built at Padstow under special survey
with a view to being classed 12A under
the mixed material Rule

Table A has been amended since
the sketch of midship section of this vessel
was approved, and the Owners request
that she might have an improved
class under the amended Table A

The whole of the frame, the beams,
the plank sheer and three strakes of
outside planking below it, are of English
Oak 12 years material, the remainder of
the outside planking and the inside
planking are of Pitch Pine 10 years
material, and the only 9 years material is
the Keelson, which is of Pitch Pine.

It is respectfully submitted that this
vessel appears worthy of the favorable
consideration of the committee to be
classed as contemplated. viz;

9 years Table A
2 years under the Mixed Material Rule.
1 year for metal fastenings.
1 year for salting.
13 A-1.

9 and 12 years material.

c.f.

salted.

B.M. J.H.

22/

7/79

