


Lloyd's Register of British & Foreign Shipping



Liverpool
December 15th 1889

This report must bear only the signature of Surveyors to Lloyd's Register of Shipping.

This is to Certify that
~~John~~ Rutherford the
undersigned Surveyor to this Society did at the
request of Messrs Harvey & Co
attend at the works of
Mr Caleb Smith junr and
1889 and subsequently to ex-
amine during construction
two steel masts intended
for Messrs Harvey & Co new
steamer No 47.

Dimensions.

Foremast: Length 73.0, diamⁱⁿ 21. Plates $7/20 \times 6/16$
Constructed with two plates
in the round, seams single,
butts triple rivetted, doubled
all round in way of decks
and fitted with two angle
bars, $3 \times 2\frac{1}{2} \times 5/16$:-

Main mast: Length 68.0, diamⁱⁿ 19. Plates $7/20 \times 6/16$
Constructed with two plates in
the round, seams single
butts triple rivetted, doubled



all round in way of deck
and fitted with two angle
bars, $2\frac{1}{2} \times 2\frac{1}{2} \times 5/16$.

The material and workman-
-ship are good.

For £ 2..2..0 John Butterford



© 2019

Lloyd's Register
Foundation

FAL135-0083(2/2)