

Proportions : Length = 3.7 Breadths = 9.99 Depths

-----CONFIRMATION-OF TELEGRAM.

47

The frames and beams are of larch 8 years material, and the outside

planking, bilge strakes, keelson, clamps and waterways are of oregon

The following is the fac-simile of a Telegram sent you this day which is
pine and larch, 9 years material.
hereby confirmed.

It is submitted that provided ceiling 2" thick be fitted in the
holds : lodging knees be fitted all fore and aft between the beams :

two additional hanging knees be fitted in view of the extreme

proportions of length to depth : the vessel be through bolted at the

joints and other parts as required by the Rules, and to the satis-

faction of the Surveyor, and be surveyed in accordance with Sections

53 and 34 : the vessel be found or placed in good condition,

and on completion be favourably reported upon, she will be worthy to

be classed SA in the Register Book, dated from 1894, the year of

build.

Ln 4.5.99

Ames. 9th

2482

J.H.S.

J.H.

9/5/99

CD

CD

CD

6910-2-0169

13740167 0166

deck