

Gross Tonnage
Residence

Wood Sailing Schooner "SENHORA DA GAYAN," No. 463 in the Register

This vessel was built at Esposende, Portugal in 1894, and has never been classed in the Society's Register Book.

The Owner now desires to obtain a class for the vessel, and has requested the Surveyor to make a preliminary examination.

Outline sketch of Midship Section, detail of disposition of framing, and preliminary report of scantlings and material submitted by Mr. Sandry.

Rule dimensions : 86 x 23.25 x 8.67

Tonnage for scantlings : 112

Proportions : Length = 3.7 Breadths = 9.99 Depths

The frames and beams are of larch 8 years material, and the outside planking, bilge strakes, keelson, clamps and waterways are of oregon pine and larch, 9 years material.

It is submitted that provided ceiling 2" thick be fitted in the holds : lodging knees be fitted all fore and aft between the beams : two additional hanging knees be fitted in view of the extreme proportions of length to depth : the vessel ^{throughout} be through bolted at the butts and other parts as required by the Rules, and to the satisfaction of the Surveyor, and be surveyed in accordance with Sections 2 53 and 34 : the vessel be found or placed in ^{all respects in} good condition, and on completion be favourably reported upon, she will be worthy to be classed 8A in the Register Book, dated from 1894, the year of build.

Ln 4.5.99

Ans'd. 9th

2 plans for rpt returned