

BK "Elvico" 646 Tons built at  
Sestri Ponente under Special Survey.

The sketch of midship section of this  
vessel was submitted and approved with  
a view to two additional years being  
assigned under the Mixed Material  
Rule, and the proportion of high class  
material was the same as in other  
vessels to which the Committee had  
granted two additional years, but it  
appears that this vessel was damaged  
to a considerable extent by fire while  
on the stocks, and although she has  
been efficiently repaired, 9 years material  
has in some instances been substituted  
for that of 12 years required by the  
Committee for the 2 additional years.

The frame is of Tuscan Oak  
and the remainder of the material  
of the 12 years grade with the exception  
of the ceiling in the 'ween decks the  
upper deck shelf clamps and spunketting,  
the lower deck waterway, the upper deck  
beams (excepting four) and four orlop beams  
which are of Larch & Pitch Pine 9 years  
material. The workmanship is "very  
good" and the vessel appears to be  
well fastened, and it is respectfully  
submitted merits the favorable considera-  
tion of the Committee for one additional  
year under the Mixed Material Rule.

viz. 9 years under Table A  
1 yr under the Mixed Material Rule  
1 yr for metal fastenings  
11 A. 1.

9 x 12 yrs matl. cf.

© 2021

Lloyd's Register  
Foundation

11/10/76 J.H.D.