

Wood Screw Steamer of about 550 Tons
to be built by Mr Durante at Genoa
with a view to class 9A-1.

Sketch of Midship Section submitted
by Mr Schiappino for the consideration of the
Committee.

Dimensions $173.83 \times 32.83 \times 15.5$
Proportions. Over 11 depths & 5 Breadths.

It is submitted that provided a
hanging knee rider be fitted to every main
deck beam, with the alternate knees in way
of the hold beams of staple form, and
long knee diagonal riders be fitted to every hold
beam, the scantlings and arrangements
as shown and amended be adhered
to, the Rules in all other respects be
complied with the vessel be built
to the satisfaction of the Society's Surveyor
and on completion be favorably reported
upon, she will be worthy to be classed
9A - as contemplated.

The Engine & Boiler bearers should be
extended well beyond the machinery space.

Lt. 19.3.91.
Ans. 26th
1 plan.

J. W

J. W.
26/3/91



© 2020

Lloyd's Register
Foundation

GEN1113-0042