

26.3.91. Barca a vapore per la costa delle Indie.

Timber and Space 26" $\frac{3}{4}$
 floors 11" $\frac{1}{2}$ x 12" $\frac{1}{2}$
 1st hull oak 9" x 9" $\frac{1}{2}$
 2nd do 8" $\frac{3}{4}$ x 8" $\frac{3}{4}$
 3rd do 8" $\frac{3}{4}$ x 8"
 Top timbers 8 x 8"
 Keel Stem Stern and
 Main Port also the
 Timbers of the Frame
 and Breasthooks
 to be of Italian
 Oak
 Remainder of
 the Material
 Pitch Pine.

Versione Maestra

Scala $\frac{1}{20}$

Dimensioni *keel beams* 8 ft apart as per rule

Lunghezza	Mo 50.00 x 2 = 53 = 173.10"
Larghezza	10.00 = 32.10"
Altezza	5.00 = 16.4"

Tonnage about 520

3 Prowers 13 $\frac{1}{2}$
 Collet Weight 38 $\frac{1}{2}$
 Stream 4 $\frac{3}{4}$
 Rods 2 $\frac{1}{2}$
 2nd do 1 $\frac{1}{2}$

Chain Cable 210 fms 1 $\frac{1}{16}$
 Stream 60 fms 13/16
 Houser 90 fms 6 $\frac{1}{2}$ 8 $\frac{1}{2}$ 4"

16" $\frac{3}{4}$ x 16" $\frac{3}{4}$ 9.0
 16" $\frac{3}{4}$ x 16" $\frac{3}{4}$ 9.0
 16" $\frac{3}{4}$ x 16" $\frac{3}{4}$ 9.0
 16" $\frac{3}{4}$ x 16" $\frac{3}{4}$ 9.0

11" x 11" 2 strakes

6 x 12

12 $\frac{1}{2}$ x 16 $\frac{3}{4}$
 Scarphs 6"

Scala clu $\frac{1}{20}$

26/3/91

Cin. Lines

Deck Shelf and 3 strakes
 of Clamps below 7" x 13 $\frac{1}{2}$ "

Hanging knee rider
 to every beam, with staple
 knee in way of hold beam
 and knee rider below.

Hold Shelf 8 x 13 $\frac{1}{2}$ "

2 strakes of Clamps
 below 8 x 13 $\frac{1}{2}$ " tapering
 at lower edge to 7"

Beams attached to the
 frames with iron straps
 and with iron H. knees

Diagonal iron plates
 1 $\frac{1}{2}$ x 5 to be fitted
 as requested by Section
 29 of the Rules.

Wood Screw Steamer
 to Elan A. 19 years



© 2020

Lloyd's Register
 Foundation

GEN1143-0048