

REPORT of SURVEY for REPAIRS.

159

No. 159 Survey held at Glasgow Date 15th December 1848
 on the Brig "Vine Blue" Master Wm. Oliver
 Tonnage 250 Built at Nova Scotia When built 1840
 By whom built 233 Owners Hannon & Co.
 Port belonging to Liverpool Destined Voyage Not Determined
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 8428 Classified A.1
 S.S. - 47 - 4. Ready

Port Liverpool

REPAIRS

At Present of Damage, Shipped a portion of the Wood Sheathing to examine for a leak, which was found in the Starboard Run (part of a seam wanted Caulking), Caulked and made good the Sheathing, Renewed the Plank sheers on each side with 4 1/2 inch Yellow Pine, Repaired the Rail and Bulwark, New Main and Fore Channel Boards and Chain Plate Bolt, Rebolled the Stern Post and Rudder Vang, Hooped the Main Mast Head, Five Pair of additional Iron Staps Nuts to the Deck and Hold Beams, Repaired and refastened the Head Rail, Caulked from the Keel to the Fourth Deck Beam.

Present Condition of the

Decks <u>in Good Condition</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>do</u>	Breasthooks and Stemson <u>do</u>	Pumps <u>2 Wood do</u>
Comings <u>do</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>2 do</u>
Upper Deck Beams & Fastenings <u>Sound & Firm</u>	Timbers of the Frame <u>do</u>	Masts, Yards, &c. <u>in Good Condition</u>
Lower Deck Beams & Fastenings <u>do</u>	Keelsons <u>do</u>	Sails <u>Complete and Good</u>
Planksheers <u>good</u>	Clamps and Shelves <u>do</u>	Anchors No. of <u>2 Br 1 Stm 1 Hedge</u>
Sheerstrakes <u>do</u>	Ceiling <u>do</u>	Cables <u>Complete and Good</u>
Topsides <u>do</u>	Rudder <u>do</u>	Hawsers and Warps <u>do do</u>
Wales <u>do</u>	Copper <u>Wood Sheathing in 4 1/2</u>	Standing & Running Rigging <u>do do</u>
Plank (Bottom) and Counter <u>do</u>		

General Observations and Opinion, This Brig is now in good condition and fit for the safe conveyance of Dry and Perishable Cargoes and may continue as Clased.

Wm. Oliver

The Amount of Fee.....£ 1 : " : " is received by me,
 Special or Damage 2 " 2 " -
 Certificate (if required) : " : "

Committee's Minute 19th Decr 1848

Character assigned Fit for service

GLS140-0147