

REPORT of SURVEY for REPAIRS.

No. 387 Survey held at Glasgow Date 24th September 1850
 on the Brig "Wanderer" Master Alexander Reddie
 Tonnage 280 Built at New Brunswick When built 1839
 By whom built 255 Owners Brown Downy & Co.
 Port belonging to Glasgow Destined Voyage Librattar
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 312 Port Glasgow Classed Expunged
 4 Not Op.

REPAIRS At present stripped the Yellow Metal Sheathing and Cleaned the Bottom, Scraped the Upper Works from the Gunwales to the Lower part of the Wale
Removed a Strake of the Inside Ceiling Plank on each side from Stem to Stem in accordance with the Rule for Special Survey
Renewed Aft in the Rung on the Starboard Side 30 First and Second Footlocks and on the Larboard Side 15 First and Second Footlocks and a number of Cheeks with Yellow Pine Vamber and the After length of Casing on each side (nearly to Abreast of the Main Mast), from the Keelson to the Hold Beam Clamps with Yellow Pine, and the Strake to the Stem and several Lengths on each Bow of Yellow Pine. A new Lower Breasthook and Pointers, 3 Pair of Additional Iron diagonal Hanging Knees to the Hold Beam, with Long Side Arms as Riders, a number of new Greenails and Deck and Hold Beam Bolts, nearly One Half of the Main Deck renewed with Yellow Pine, Caulked from the Keel to the Wale and Decks; Upper Works Caulked about Four Months since; Sheathed the Bottom with Zinc over Paper to the 12 feet Water Line

Present Condition of the

Decks <u>In Good Condition</u>	Treenails <u>Good</u>	Windlass and <u>Capstan</u> <u>Good</u>
Waterways <u>do</u>	Breasthooks and Stemson <u>do</u>	Pumps <u>2</u> <u>do</u>
Comings <u>do</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>3</u> <u>do</u>
Upper Deck Beams & Fastenings <u>Sound & Firm</u>	Timbers of the Frame <u>do</u>	Masts, Yards, &c. <u>In Good Condition</u>
Lower Deck Beams & Fastenings <u>do</u>	Keelsons <u>do</u>	Sails <u>Complete and Good</u>
Planksheers <u>Good</u>	Clamps and Shells <u>do</u>	Anchors No. of <u>3 Bx 1 Star 1 Kedge</u>
Sheerstrakes <u>do</u>	Ceiling <u>do</u>	Cables <u>Complete and Good</u>
Topsides <u>do</u>	Rudder <u>do</u>	Hawsers and Warps <u>do</u> <u>do</u>
Wales <u>do</u>	<u>Copper Zinc</u> When put on <u>Sept. 1850</u>	Standing & Running Rigging <u>do</u> <u>do</u>
Plank (Bottom) and Counter <u>do</u>		

General Observations and Opinion No now in good Condition and Eligible for the safe Conveyance of Dry and Perishable Cargoes and may be Reclafed 4 Ft. 1.
S. S. = 50 = 4 Cans,


The Amount of Fee.....£ 1 : : : is received by me,

Special..... 2 : 2 : :

Certificate (X required) : 10 : :

Committee's Minute 27th Sept. 1850

Character assigned 1st Class



© 2019
 Lloyd's Register
 Foundation

5950-01575