

REPORT of SURVEY for REPAIRS.

489

Re Entry Rec 10/7/57

No. 489 Survey held at Glasgow Date 8th July 1857
 12 on the Ship "Hallyards" Master Joseph Potts
 Tonnage 299 Built at Port Glasgow When built 1818
 By whom built _____ Owners Campbell & Co.
 Port belonging to Glasgow Destined Voyage Demerara
 If Surveyed Afloat or in Dry Dock Patent Slip

Rest 38 - 6 Yrs C. 2 *A. 1 SS. 48

Last Survey, No. 2913 Port Glasgow Classed Expunged
 REPAIRS At Present stripped the Yellow Metal Sheathing and Cleanned the Bottom
Renewed Two Broken Hold Beams Iron Hanging knees and the Throat Bolt to the
others driven out and Renewed
Caulked from the Keel to the Wales and Reheathed the Bottom with Yellow Metal over
Part Paper and Part Felt

Present Condition of the

Decks <u>Good Condition</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>dr</u>	Breasthooks and Stemson <u>dr</u>	Pumps <u>2 Main & 2 Bidge dr</u>
Comings <u>dr</u>	Transoms, Pointers, and Crutches <u>dr</u>	Boats <u>3 dr</u>
Upper Deck Beams & Fastenings <u>Sound & Firm</u>	Timbers of the Frame <u>(When Seen) dr</u>	Masts, Yards, &c. <u>Complete & Good</u>
Lower Deck Beams & Fastenings <u>Firm</u>	Keelsons <u>dr</u>	Sails <u>dr dr</u>
Planksheers <u>Good</u>	Clamps and Shelves <u>dr</u>	Anchors No. of <u>3 B. 1 Str. 1 Kedge</u>
Sheerstrakes <u>dr</u>	Ceiling <u>dr</u>	Cables <u>Complete and Good</u>
Topsides <u>dr</u>	Rudder <u>dr</u>	Hawsers and Warps <u>dr dr</u>
Wales <u>dr</u>	Copper <u>Yellow Metal When put on July 1851</u>	Standing & Running Rigging <u>dr dr</u>
Plank (Bottom) and Counter <u>dr</u>		

General Observations and Opinion This Ship is in good Condition and fit for the safe Conveyance of dry
and Perishable Cargoes to and from all parts of the World and may be Reclasped *A, 1,
with the Asterisk

The Amount of Fee.....£ 1 : : is received by me,

Special..... : : :

Certificate (if required) : : :

Committee's Minute 11th July 1857

Character assigned Fit for Service