

# REPORT of SURVEY for REPAIRS.

564

No. 564 Survey held at Glasgow Date 21<sup>st</sup> January 1852  
 on the Ship "Catherine" Master James Morris  
 Tonnage 222 Built at Wundelund When built 1828  
 By whom built \_\_\_\_\_ Ownery Henderson  
 Port belonging to Glasgow Destined Voyage Trinidad  
 If Surveyed Afloat or in Dry Dock Patent Slip

last Survey, No. 369 Port Glasgow Classed 7<sup>th</sup> A. 1 SS 48

REPAIRS At Present of damage and for Clipping, Scraped the Upper Works  
from the Lower Part of the Walls to the Gunwales  
stripped the Yellow Metal Sheathing and Cleaned the Bottom, Renewed a  
number of Greenails and Hold Beam Knee and Ricker Bolts and One Hold  
Beam and Knee  
repaired the Bulwark and Rail, One Hanging Knee to a Deck Beam  
renewed being Broken  
Painted over all and Re-sheathed with Yellow Metal over Felt

Present Condition of the

Decks <u>in Good Condition</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>do</u>	Breasthooks and Stemson <u>do</u>	Pumps <u>2</u> <u>do</u>
Omings <u>do</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>2</u> <u>do</u>
Upper Deck Beams & Fastenings <u>Sound &amp; Firm</u>	Timbers of the Frame <u>do</u>	Masts, Yards, &c. <u>Complete &amp; Good</u>
Lower Deck Beams & Fastenings <u>Firm</u>	Keelsons <u>do</u>	Sails <u>do</u> <u>do</u>
Planksheers <u>Good</u>	Clamps and Shelves <u>do</u>	Anchors No. of <u>3 1/2</u> <u>Stems &amp; Rudder</u>
Steerstrakes <u>do</u>	Ceiling <u>do</u>	Cables <u>Complete and Good</u>
Oppsides <u>do</u>	Rudder <u>do</u>	Hawsers and Warps <u>do</u> <u>do</u>
Tales <u>do</u>	Copper <u>Yellow Metal</u> When put on <u>Jan<sup>y</sup> 1852</u>	Standing & Running Rigging <u>do</u> <u>do</u>
Plank (Bottom) and Counter <u>do</u>		

General Observations and Opinion, We have specially surveyed this vessel in accordance with the  
only Section 60 and is now in good Efficient Condition and are mutually of  
opinion that she may continue as Classed 7<sup>th</sup> A. 1.

The Amount of Fee.....£ 1 : 4 : 0 is received by me,

Special Rate 4 : 4 : 0  
 Special on damage 2 : 2 : 0  
 Certificate (if required) 0 : 10 : 0

Committee's Minute 3rd Feb<sup>y</sup> 1852

Character assigned F 1 / 1



© 2019

Lloyd's Register  
Foundation

GLS141-0052