

REPORT of SURVEY for REPAIRS.

575

No. 575 Survey held at Glasgow Date 12th February 1852
 on the Barge Emma Master R. S. Wakefield
 Tonnage 308 Built at Hull When built 1826
 By whom built _____ Owners V. Smith
 Port belonging to Liverpool Destined Voyage Gemerara
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 11137 Port Lpool Classed 10.F.1
 REPAIRS For Special Survey Net 42, 7. Gear, Cont. 49.2 Gear

Scrapped the Upper Works right from the Lower part of the Wale to the Gunwale, threw out Greening and Deck and Hold Beam Bolt for Inspection which were found good and renewed Scruped One End of an After Hold Beam and renewed One Lodging Knee, Re-fastened the Rudder Braces and Pintles, patched and repaired the Yellow Metal on the Lower part of the Keel Stripped the Head Knee Cheek and Hauser Piece to Caulk the Hooding Ends and Seam below; renewed Nine Bulwark Stanchion on the Starboard Side and Ten on the Larboard Side, repaired the Bulwark and Rail and renewed the Head Cheek, Rail and Hauserpiece

| | | | |
|-------------------------------|--------------------------|--|----------------------------|
| Present Condition of the | | | |
| Decks | <u>Ch Good Condition</u> | Treenails | <u>Good</u> |
| Waterways | <u>do</u> | Breasthooks and Stemson | <u>do</u> |
| Comings | <u>do</u> | Transoms, Pointers, and Crutches | <u>do</u> |
| Upper Deck Beams & Fastenings | <u>Sound</u> | Timbers of the Frame | <u>do</u> |
| Lower Deck Beams & Fastenings | <u>Firm</u> | Keelsons | <u>do</u> |
| Plank sheers | <u>good</u> | Clamps and Shells | <u>do</u> |
| Heerstrakes | <u>do</u> | Ceiling | <u>do</u> |
| Opsides | <u>do</u> | Rudder | <u>do</u> |
| Vales | <u>do</u> | Copper <u>Pl Metal</u> When put on <u>1850</u> | |
| Plank (Bottom) and Counter | <u>Where Sound</u> | Windlass and Capstan | <u>Good</u> |
| | | Pumps | <u>2 Metal do</u> |
| | | Boats | <u>3 do</u> |
| | | Masts, Yards, &c. | <u>do</u> |
| | | Sails | <u>do</u> |
| | | Anchors No. of <u>3 Br 1 Str 1 Rudge</u> | |
| | | Cables | <u>Complete & Good</u> |
| | | Hawsers and Warps | <u>do do</u> |
| | | Standing & Running Rigging | <u>do do</u> |

General Observations and Opinion, We have Surveyed this Barge Carefully in Accordance with the Rules Section 54 & 60, and are mutually of opinion that she may be classed 10.F.1.


The Amount of Fee.....£ 2 : : : is received by me,

Special..... 4 : 4 : :

Certificate (if required) : : 10 : :

Committee's Minute 24th Feb 1852

Character assigned FA 11



© 2019

Lloyd's Register Foundation
GLS 141-0061