

REPORT of SURVEY for REPAIRS.

No. 673 Survey held at Glasgow Date 4th January 1853
 28 on the Big Wanderer Master William Neave
 Tonnage 280 Built at New Brunswick When built 1839
 By whom built 255 Owners Brown Downes & Co
 Port belonging to Glasgow Destined Voyage Albion
 If Surveyed Afloat or in Dry Dock Patent Ship

Last Survey, No. 579 Port Glasgow Classed 4 Feb. 1892
S. S. 50, 49

REPAIRS

REPAIRS At Present Stripped the fine Sheathing off the Bottom
Renewed the lower Stake of Wale on each Side from the Luff of the Bow
to the Quarter with American Rock Elm and all the Hold Beam Binding
Bolts, and the Fore Piece of Keel and Gripe with Black Birch; Fore
Shift of Starboard Stake and the one next above the Starboard Stake
renewed with Rock Elm, Some new Ceiling on the Bow, the wider Keelson
betwixt the Fore and Main Mast 3 inches double of Elm
Caulked over all and Sheathed the Bottom with Yellow Metal over
Selt to the Wale

Present Condition of the

Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	do	Breasthooks and Stemson	do	Pumps	2 Metal do
Comings	do	Transoms, Pointers, and Crutches	do	Boats	3 do
Upper Deck Beams & Fastenings	Sound	Timbers of the Frame	When seen do	Masts, Yards, &c.	do
Lower Deck Beams & Fastenings	Firm	Keelsons	do	Sails	Complete and Good
Planksheers	good	Clamps and Shelves	do	Anchors	No. of 3 1/2 1 Stone 1 Kedge
Sheerstrakes	do	Ceiling	do	Cables	Complete and Good
Topsides	do	Rudder	do	Hawsers and Warps	do do
Wales	do	Copper	When put on Aug. 1853	Standing & Running Rigging	do do
Plank (Bottom) and Counter	do				

General Observations and Opinion, *Is in good Condition and fit for the safe Conveyance of
Dry and Perishable Cargoes and may continue as Chased*

The Amount of Fee.....£ / : : is received by me,

Special..... 4 : 2 : 5

Certificate (if required) " : " : "

Committee's Minute 11th Jan^y 1853

Character assigned



© 2019

Lloyd's Register
Foundation

GLS 141-0146