

REPORT of SURVEY for REPAIRS.

Rec. 17/2/53

No. 686 Survey held at Glasgow Date 14th February 1853
 on the Schooner Agnes Master John Battershall
 Tonnage 137 Built at Greenock When built 1838
 By whom built 125 Owners Brown & Co
 Port belonging to Glasgow Destined Voyage Leaving
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 15026 Port London Classed Expunged

REPAIRS Scraped the Upper Works Clean from the Gunwale to the Lower Part of the Wale, Drove out several Greenails and Beam Bolts for Inspection; Renewed a number of Deck Beam Bolts. Gubbed Clean the Ceiling in the Hold from the Clamps to the Ridges. Renewed Three Planks of Ceiling and some pieces with Yellow Pine, Caulked from the Sheathing to the Gunwale. It appears that in August 1852 this Schooner had her Yellow Metal Sheathing stripped at Japan S. P. and the Bottom, Waterways and Deck Caulked and the Bottom Sheathed with Copper over Felt.

Present Condition of the

Decks <u>Good</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>do</u>	Breasthooks and Stemson <u>do</u>	Pumps <u>2 Metal do</u>
Comings <u>do</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>2 do</u>
Upper Deck Beams & Fastenings <u>Sound</u>	Timbers of the Frame <u>Where seen do</u>	Masts, Yards, &c. <u>do</u>
Lower Deck Beams & Fastenings <u>Firm</u>	Keelsons <u>do</u>	Sails <u>do</u>
Planksheers <u>Good</u>	Clamps and Shelves <u>do</u>	Anchors No. of <u>20 3/4 1 Stem 1 Hedge</u>
Sheerstrakes <u>do</u>	Ceiling <u>do</u>	Cables <u>Complete & Good</u>
Topsides <u>do</u>	Rudder <u>do</u>	Hawsers and Warps <u>do do</u>
Wales <u>do</u>	Copper <u>Good</u> When put on <u>1852</u>	Standing & Running Rigging <u>do do</u>
Plank (Bottom) and Counter <u>Where seen do</u>		

General Observations and Opinion, We have Specially Surged this Schooner in accordance with the Rules Section 54 & 60, in good Condition and fit for the safe Conveyance of Dry and Perishable Cargoes to and from all ports. We are mutually of opinion that she may be Classed S.E. with the distinction of the Asterisk.

The Amount of Fee.....£ : 10 : " is received by me,

Special..... 4 : 4 : "


Certificate (if required) " : 5 : "

Committee's Minute

Character assigned

18th Feb 1853

TR 1, 1



© 2019
Lloyd's Register
Foundation

GLS141-0157