

REPORT of SURVEY for REPAIRS.

1214

Rev 20/6/56

No. 1214 Survey held at Penzance Date 29th May 1856
 on the Barge Agricola Master James Bell
 Tonnage 472 Built at Cundinland When built 1839
 By whom built 564 Owner Alexander Adamson
 Port belonging to London Destined Voyage Not known
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 18733 Port London Classed S.P. 1 S.S. 54
 C 3 34

REPAIRS Off Damage at Maulmain in 1855, Ship having run on shore
on her outward voyage, stripped the Yellow Metal Sheathing and
Caulked the Bottom

Renewed 120 Chocks at the head and heels of timbers, Nine Strakes
of Plating in the Hold of Length 5 In. Side Keelsons of Length 9 x 8 1/2
Greenails all renewed; Upper and Lower Deck Fastenings on the
Starboard Side; Caulked over all & sheathed the Bottom with
Zinc over Chinam

The Master states that the above took place at an expense of nearly
£2000

29th May 1856 At the request of the Owner Surveyed the Bottom
for the purpose of ascertaining the state of the Zinc Sheathing
Found it much wrinkled and 94 sheets on the Starboard side and
59 on the Starboard side entirely gone and every appearance of the ship
having strained; Recommended the keel to be stripped and
P. I. O.

Present Condition of the

Decks	✓	Treenails	✓	Windlass and Capstan	✓
Waterways	✓	Breasthooks and Stemson	✓	Pumps	✓
Comings	✓	Transoms, Pointers, and Crutches	✓	Boats	✓
Upper Deck Beams & Fastenings	✓	Timbers of the Frame	✓	Masts, Yards, &c.	✓
Lower Deck Beams & Fastenings	✓	Keelsons	✓	Sails	✓
Planksheers	✓	Clumps and Shelves	✓	Anchors No. of	✓
Sheerstrakes	✓	Ceiling	✓	Cables	✓
Topsides	✓	Rudder	✓	Hawsers and Warps	✓
Wales	✓	Copper <u>Zinc</u> When put on <u>1855</u>		Standing & Running Rigging	✓
Plank (Bottom) and Counter	✓				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

On consequence of the Owner declining to carry out the requirements of
the Rules Section 60. I beg to recommend that the Ship's Character
be Expunged

The Amount of Fee.....£ : : is received by me,

Special Damage 2: 2: "

Certificate (if required) " : : "

Committee's Minute 24th June 1855

Character assigned Expunge Character

Genl Com: Minute
3 July 1856
claiming confirmed

Notice to owner
L. J. 25 June 56

undergo a Special Survey; the latter the Owner is not
disposed to attend to at present; until the vessel has
made another voyage //



© 2019

Lloyd's Register
Foundation