

1348

Rec 21/5/57

REPAIRS
Of Damage; Stripped the Yellow Metal Sheathing, Cleaned the
Bottom and Spotted the Viseide,
Renewed several Viseide Planks on each side with Baltic Oak
and two Bulwark Stanchions; Scarphed two Upper Deck and
one Hold Beam; Sheathed the Upper Deck from Stem to Rined
Quarter Deck with 1 1/2 in. Yellow Pine over part Felt
Renewed some pieces of Ceiling Plank in Hold with Baltic Oak,
a number of Greenaid in Viseide and Bottom and deck and Hold
Beam Knee Bolts; Chunnel Bolts and Chain Plates
New Rider Nelson from Main to Fore Mast American Elm
Caulked from Keel over all

Decks	<i>Good</i>	Treenails	<i>Part New & Good</i>	Windlass and Capstan	<i>Good</i>
Waterways	<i>do</i>	Breasthooks and Stemson	<i>Good</i>	Pumps	<i>2 do</i>
Comings	<i>do</i>	Transoms, Pointers, and Crutches	<i>do</i>	Boats	<i>2 do</i>
Upper Deck Beams & Fastenings	<i>do</i>	Timbers of the Frame	<i>Whole New do</i>	Masts, Yards, &c.	<i>do</i>
Lower Deck Beams & Fastenings	<i>do</i>	Keelsons	<i>do</i>	Sails	<i>do</i>
Planksheers	<i>Good</i>	Clamps and Shelves	<i>do</i>	Anchors	No. of <i>312 10 lbm. 100 lbm.</i>
Sheerstrakes	<i>do</i>	Ceiling	<i>do</i>	Cables	<i>Good</i>
Topsides	<i>Part New & do</i>	Rudder	<i>do</i>	Hawsers and Warps	<i>do</i>
Wales	<i>do</i>	Copper	<i>Partial When put on May 5th</i>	Standing & Running Rigging	<i>do</i>
Plank (Bottom) and Counter	<i>do</i>				

Caulking of Bottom, Deck, & Waterways.

Is now in good Condition fit for the safe Conveyance of Dry and
perishable Cargoes to and from all parts of the World and may continue
as Chartered

May 18

Certificate (if required) " : : =

Character assigned

Rest 8 1/2

Record damage given



© 2019

Lloyd's Register
Foundation

GLS142-0137