

REPORT of SURVEY for REPAIRS.

No. 1642 Survey held at Glasgow Date 25th February 1860
 on the Schooner Orca Master Peter M^r Arthur
 Tonnage 208 Built at Glasgow When built 1844
 By whom built — Owners M^r Arthur Peabody
 Port belonging to Glasgow Destined Voyage Liverpool
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 4005 Port Clyde Classed 10 Δ
 Cont 57 8 2,59

REPAIRS Damage, Scarfed a piece on Fore End of Keel
Renewed the Gripe and False Stem, Vimed fair the Lower Side
of Keel and reclinched the Bolt, Fitted a 3 Inch False Keel from
End to End well Bolted diagonally to Main Keel, New Angle Iron on
the Lower Corners; renewed on the Starboard Bow two Fore Shifts of
Bottom Plank and Aft on the Starboard Side on the Flat two
Planks of American Pitch Elm, a number of Greenails and Butt and
Bidge Bolt; Caulked from Keel to Gunwale

Present Condition of the

Decks	<i>Good</i>	Treenails	<i>Good</i>	Windlass and Capstan <i>Winch</i>	<i>Good</i>
Waterways	<i>do</i>	Breasthooks and Stemson	<i>do</i>	Pumps	<i>2 do</i>
Comings	<i>do</i>	Transoms, Pointers, and Crutches	<i>do</i>	Boats	<i>2 do</i>
Upper Deck Beams & Fastenings	<i>3 Sound</i>	Timbers of the Frame	<i>do</i>	Masts, Yards, &c.	<i>Complete & Good</i>
Lower Deck Beams & Fastenings	<i>3 Firm</i>	Keelsons	<i>do</i>	Sails	<i>do do</i>
Planksheers	<i>Good</i>	Clamps and Shelves	<i>do</i>	Anchors	No. of <i>3 B. 1 Stem Wedge</i>
Sheerstrakes	<i>do</i>	Ceiling	<i>do</i>	Cables	<i>Complete & Good</i>
Topsides	<i>do</i>	Rudder	<i>do</i>	Hawsers and Warps	<i>do do</i>
Wales	<i>do</i>	Copper	<i>Single When put on Bottom</i>	Standing & Running Rigging	<i>do do</i>
Plank (Bottom) and Counter	<i>do</i>				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Is now in good and efficient Condition fit for the safe Conveyance of dry
and Buichable Cargoes to and from all parts of the World and may Continue
as afloat

The Amount of Fee.....£ 4 : 10 : 0 is received by me,

Special..... 4 : 4 : 3

Certificate (if required) : : :

Committee's Minute 6th March 1860

Character assigned Cont 3 1/2

record damage repair



© 2019

Lloyd's Register
Foundation

GLS 142 - 0353