

REPORT of SURVEY for REPAIRS.

1971

No. 1971 Survey held at Glasgow Date 17th November 1862
 on the Ship "Caledonia" Master Robert Carrance
 Tonnage 383 Built at Greenock When built 1841
 By whom built ✓ Owners Allan & Co.
 Port belonging to Glasgow Destined Voyage Matanzas
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 1863 Port Glasgow Classed 10 1.62

REPAIRS

Stripped the Yellow Metal & Wood Sheathing, Brightened the Bottom
 Scraped Clean from the Light Water Mark to the Waterways Included.
 Gave out Greenails & Beam Bolts for Examination which were found good
 and renewed
 Renewed, Upper piece of Opson of American Oak, Throat Bolt of the
 Four Upper Hooks of Iron, Wood End Bolt in Way of same of Yellow Metal
 and Iron, One Breasthook of Baltic Oak, Nine Second Gutstocks and Six
 First in After End of American Oak
 Two Lengths of Main Nelson in Midships of American Oak and Fastened
 with Iron, Thirty Planks of Ciling on Starboard Side in Flat of Bottom
 and Bilge, Thirty Six on the Port Side of American Oak, Red Pine and
 Birch Elm, Remainder of Ciling in Hold Dabbed Bright and Repaired
 the whole of the Iron Bolt to Hold Beam Lodging Piece of Iron; Piece of
 Head refitted and fastened, One Plank of Upside German Oak
 Keel recaulked from Keel to Gunwale and Bottom Sheathed with Yellow

Present Condition of the

Decks	<u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	<u>do</u>	Breasthooks and Stenson	<u>do</u>	Pumps	<u>do</u>
Comings	<u>do</u>	Transoms, Pointers, and Crutches	<u>do</u>	Boats	<u>do</u>
Upper Deck Beams & Fastenings	<u>do</u>	Timbers of the Frame	<u>do</u>	Masts, Yards, &c.	<u>do</u>
Lower Deck Beams & Fastenings	<u>do</u>	Keelsons	<u>do</u>	Sails	<u>do</u>
Planksheers	<u>do</u>	Clamps and Shelves	<u>do</u>	Anchors No. of <u>3 1/2 1st in Wedge</u>	
Sheerstrakes	<u>do</u>	Ceiling	<u>do</u>	Cables	<u>Good</u>
Topsides	<u>do</u>	Rudder	<u>do</u>	Hawsers and Warps	<u>do</u>
Wales	<u>do</u>	Copper <u>Yellow Metal</u> When put on <u>1862</u>		Standing & Running Rigging	<u>do</u>
Plank (Bottom) and Counter	<u>do</u>				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Specially Surveyed in Accordance with the Rules Section 54, is in good and
 efficient condition fit for the safe conveyance of Dry and Perishable
 Cargoes to & from all parts and in our opinion may be Continued A.T. for
 2 Years from 1862

The Amount of Fee.....£ 4 : : : is received by me,

Special..... 4 : 4 : :

✓ Certificate (if required) " : 5 : :

Committee's Minute 28th November 1862

Character assigned Conf. 1 for 2 years

B. Darling
H. Wood
 © 2019
 Lloyd's Register
 Foundation
 GLS143-0136

1971 Geo

Metal on Felt to the Lower part of Wales
Windlass Shipped Examined and Relined

A. Darling
H. P. Boulders.



© 2019

Lloyd's Register
Foundation