

2496

REPORT of SURVEY for REPAIRS.

Rec 25/6/66

No. in Reg. Book. **No. 2496** Survey held at Glasgow Date 2^d June 1866
55 on the Brigantine "Acanthes" Master J. Roberts
Tonnage 18⁴ Built at Prince Edward Island When built 1858
By whom built Owner J. Roberts
Port belonging to London Destined Voyage Alexandria
If Surveyed Afloat or in Dry Dock Abt. Stephen & Son Patent Slip

Last Survey, No. 8378 Port Newcastle. Classed 7 Δ Δ expired 61

REPAIRS The fine Sheathing entirely stripped, Bottom Gubbed Bright
Samped from thence to Waterway included; A Strake of Plank split
out fore and aft at Turn of Ridges inside and Listings at Ends
Windlass unbung, stripped, examined and found good, Bolts and
Greenails shifted out and Section 54 & 63 fully Complied with
Cepel Re-caulked from Keel to Gunwale & Sheathed with fine or felt to Wales
Chain Cables ranged on Deck and found good and sufficient
Bolts and Greenails shifted out for inspection renewed
Two Strakes of Ceiling Split out for Survey at Turn of Ridges renewed
with Red Pine

Present Condition of the

Decks <u>Where Seen Good</u>	Treenails <u>Where Seen Good</u>	Windlass and <u>Capstan</u> <u>Good</u>
Waterways <u>do</u>	Breasthooks and Stemson <u>do</u>	Pumps <u>do</u>
Comings <u>do</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>do</u>
Upper Deck Beams & Fastenings <u>do</u>	Timbers of the Frame at the openings <u>do</u>	Masts, Yards, &c. <u>do</u>
Lower Deck Beams & Fastenings <u>do</u>	Ditto Ditto at other places <u>do</u>	Condition, how ascertained <u>from examination</u>
Planksheers <u>do</u>	Keelsons <u>do</u>	Sails <u>Complete</u>
Sheerstrakes <u>do</u>	Clamps and Shelves <u>do</u>	Anchors No. of <u>2 B & 1 Star & 1 Wedge</u>
Topsides <u>do</u>	Ceiling <u>do</u>	Cables <u>Complete</u>
Wales <u>do</u>	Rudder <u>do</u>	Hawsers and Warps <u>do</u>
Plank (Bottom) and Counter <u>do</u>	Copper <u>fine</u> When put on <u>1866</u>	Standing & Running Rigging <u>do</u>

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. New & Good where tested

Specialy Surveyed in accordance with the Rules Section 63 and First Clause
of Section 54, As in good and efficient Condition Eligible in our opinion
to be Continued A. 1. for 2 Years from 1865
S. S. 66. 5 Years

The Amount of Fee.....£ 2 : : is received by me.

Special..... 4 : 4 :
Certificate (if required) : : 2 : 6

Committee's Minute 26th June 18 66

Character assigned Cont A 1 for 2 Years
Record fine. S. S. 66 = 5 Years

B. Darling
J. W. Nettle



© 2019
Lloyd's Register
Foundation
GLS43-0468