

Completion of Periodical Survey Sec 43. for Composite Ships  
**ANNUAL SURVEYS.**

4809

Report No- 4809

In Register - No. 321 Survey held at Glasgow Date 26<sup>th</sup> Feb 1879  
 on the S. "Otago" Master R. Peebles  
 Tonnage 993 Built at Port Glasgow When built 1869 - 8 mo.  
 By whom built Duncan Owners Albion Sh. Co.  
 Port belonging to Glasgow Destined Voyage New Zealand.  
 If Surveyed Afloat or in Dry Dock On Pinnthouse Ship and Afloat

Last Survey, No. 19 Port of Dunedin Classed 17 A1  
 (Dunedin Report No 19 herewith) S. S. Clz. 73 1/78

The present Condition of the

Decks	<u>Good</u>	<del>Timber</del> Balbs	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	<u>do</u>	Breasthooks and Stemson	<u>do</u>	Pumps	<u>Overhauled and made Good</u>
Comings	<u>do</u>	Transoms, Pointers, and Crutches	<u>do</u>	Boats	<u>5 no. Good</u>
Upper Deck Beams & Fastenings	<u>do</u>	<del>Ways</del> of the Frame at the Openings	<u>do</u>	Masts, Yards, &c.	<u>do</u>
Lower Deck Beams & Fastenings	<u>do</u>	<del>Ways</del> ditto at other places	<u>do</u>	Sails ( <u>10 new pieces now supplied</u> )	<u>Well Found</u>
Planksheers	<u>do</u>	Keelsons	<u>do</u>	Anchors, No. of	<u>3 B. 1 S. 2 R</u>
Sheerstrakes	<u>do</u>	<del>Planks</del> and Shelves <u>Securitus</u>	<u>do</u>	Cables	<u>Complete</u>
Topsides	<u>do</u>	Ceiling	<u>do</u>	Hawsers and Warps	<u>90 faths 10<sup>in</sup> now supplied 75 well found</u>
Wales	<u>do</u>	Rudder	<u>do</u>	Standing and Running Rigging	<u>now overhauled, in good order</u>
Plank (Bottom) and Counter	<u>do</u>	Copper <u>Yellow Metal</u> When put on <u>1878</u>			

General Observations and Opinion,

Caulking of Bottom, Deck, and Waterways as far as seen, Good.

Referring to Glasgow Report No 4607 and Dunedin Report No 19, the remaining six galvanized iron screw bolts in middle line through Keel Plate have been renewed with Yellow Metal bolts. - Bottom sighted, yellow metal sheathing patched. - New Fore topgallant mast, fore topmast backstays and stays, and Sit Guys, Steering Gear and Pumps overhauled and made good. All the requirements of Sec. 43 for Periodical Survey for Composite Vessels having now been completed, she is eligible to Committee's Minute 7th March, 1879, as classed and marked S. S. Clz. - 78

Character assigned

GLS145-0183

17 A1

Wm Saml. Laphorn

Certificate (if required).

S.S. 78 N.E. 78