

REPORT of SURVEY for REPAIRS, &c.

4833

No. 1803 Survey held at Glasgow Date, first Survey 14 April Last Survey 2nd April 1879
 Reg. Book. 156 on the Brig "Patra" Master Wm Richards
 TONNAGE under Tonnage Deck 103.53 Built at Brisbane When built 1864
 Ditto of Spar Deck, or Awning Deck Owners D Richards Port belonging to Brisbane
 Ditto of Poop Residence Portmadoc
 Ditto of Raised Qr. Dk. By whom built Dewdney Destined Voyage By Berbee
 Ditto of Houses on Deck If Surveyed Afloat or in Dry Dock Walsingham Slipway
 Ditto of Forecastle Gross Tonnage 104
 Crew Space, as per Rule Register Tonnage, cut on Beam 104
 Engine Room Reg. Tons as St' mer, cut on Bm.
 Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft. Years assigned. Character in Register Book.
 Last Survey, No. 1803 Port Portmadoc Classed 1st A. 1
Cont'd June 76. 4
6.77

REPAIRS, OR EXAMINATION AS PER RULE

In anticipation of Continuation Second rule
 The yellow metal sheathing stripped off. The outside plank
 dished right up to 11 feet forward and 12 feet aft treenails in
 that range driven out for survey and found good. Iron bolts in
 knees, above that height driven out found wasted and renewed.
 The bottom caulked and resheathed with yellow metal on felt

Cause of Repairs to be clearly stated.


Present Condition of the						
Decks	Good	Treenails	driven out	Good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stemson	not cleared	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	from deck
Planksheers	"	Keelsons	Good	"	Sails	said to be complete
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors	No. of 2 B. 15 M
Topsides	"	Ceiling	"	"	Cables	said to be complete
Wales	"	Rudder	"	"	Hawsers and Warps	insufficient
Plank (Bottom) and Counter	"	Copper	When put on 4.79	"	Standing & Running Rigging	Good
Engine Room Skylights	"	Caulking of	"	"	Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	Good	"	Hatches	Good
Scuppers	"					

General Observations, Opinion as to Class, &c.
 This vessel is in good and efficient condition eligible to
 remain as classed AS

The Amount of Entry Fee£ : : : received by me, }
 Special£ 1 : 1 : April 1879 }
 Certificate (if required)£ : : :
 (Travelling Expenses, if any, £)

Committee's Minute 15th April, 1879.
 Character assigned
 Approved by
 J. B. W. 1879

W. J. ...
 Surveyor to Lloyd's Register of British and Foreign Shipping.



[4,000-18,678.]