

# Report of Survey for Repairs of Engines and Boilers.

No. 5557

(Received at London Office, 5/11/87)

No. in Reg. Book. Survey held at Glasgow

Date, first Survey Mar 17th Last Survey Dec 31st 1881

555 on the Machinery of the Screw Steamer "Marguerite"

(Number of Visits 1)

Tonnage, Gross 296

Built at Port Glasgow

When built 1872

Ditto, Net 470

Owners Charles Henderson & Co

Port belonging to Glasgow

Diameter of Cylinder 22" x 40"

Engines made by Kincaid & Co

When made 1872

Length of Stroke 27"

Boilers made by Lobnitz, Coulborn & Co

When made 1876

Pressure of Steam 40 lbs

If Surveyed Afloat or in Dry Dock Both

Classed 90. A1

Registered Horse Power 40

Last Survey No. 5557

Port Glasgow

Lloyd's M.B. 6.78

Particulars of Repairs and Examination Cylinders opened up, Pistons & slide valves examined & overhauled, pumps, pipes & roses cleaned, repaired & put in working order. Crank shaft with bearings examined, sea connections overhauled. Engine Room bulkhead made watertight by fitting bolts in movable plate to permit of the Condenser Lifter being drawn.

Main Boiler (fitted on board in 1878) cleaned & examined throughout. Several rivets renewed in the furnace mouths & some of the cocks & connections re-jointed & made good.

Donkey Boiler, examined, found in good condition.

General Observations, Opinion, and Recommendation:—The Machinery & Boilers of this vessel are now in good working condition and eligible in my opinion to be noted in the Register Book. Lloyd's M. B. 12.81

Entry or Registering Fee £ 0:0:0  
Survey Fee ... £ 3:3:0  
Certificate (if required) .. £ 0:0:0

received by me, 2/12/87

(Travelling Expenses, if any, £ )

Committee's Minute

6/1/02 188

Assigned

Lloyd's M. B. 12.81

James Morrison, Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Glyde District

Lloyd's Register of Shipping

GLS 146-0181

(Continuation of Engines and Boilers, and subsequent Repairs and Examinations, to be clearly stated.)

(Engineers are requested not to write on or below the space for Committee's Minute.)



5357 980

It is submitted that the vessel is  
not to be used for the purpose of  
transporting passengers or cargo  
and is to be used for the purpose of  
transporting passengers or cargo  
as per rule

11/1/02



© 2019

Lloyd's Register  
Foundation