

Report of Survey for Repairs of Engines and Boilers.

No. 5564

(Received at London Office, 12/12/81)

No. in Reg. Book. 220 Survey held at Glasgow Date, first Survey Dec 6th Last Survey Dec 8th 1881

on the Machinery of the *S.S. "Pemburgh"* (Number of Visits 2)
 Tonnage, Gross 818 Built at Port. Glasgow When built 1878
 Ditto, Net 576 Owners H. L. Seligmann & Co. Port belonging to Glasgow
 Diameter of Cylinder 25" x 44" Engines made by Blackwood & Gordon When made 1870
 Length of Stroke 30" Boilers made by Do. When made 1870
 Pressure of Steam 45 lb. If Surveyed Afloat or in Dry Dock Afloat. (State name of Dock.)
 Registered Horse Power 90 Classified A 1
 Last Survey No. 4652 Port Shk. Date 8.12.81

Particulars of Repairs and Examination In consequence of age and Condition of Main Boiler.

On examination found shell plating and stays in steam space corroded in several places. Also bottoms of furnaces at back ends. and bottoms of backs and sides of Combustion Chamber plating. Tube plates and tubes found in fair condition. Bottom landings of shell overhauled and caulked in places where found leaking. Fitted new rivets (about 14 in number) in the landings of furnaces. and the boiler inside thoroughly cleaned and sealed. This boiler is in my opinion safe for a working pressure of 45 lbs to which the spring safety valves have been adjusted.

General Observations, Opinion, and Recommendation:— The Machinery as far as steam and Main Boilers are in a safe working condition and eligible for one voyage ending about the middle January next. The Owners having arranged to lay the vessel up at that time to receive new Main and Bottom Boilers.

Entry or Registering Fee, £ 0: 0: 0
 Survey Fee (per Section 28) £ 1: 1: 0 received by me, *W. Gregor*
 Certificate (if required) £ 0: 0: 0 10th Dec 1881
 to be sent as per margin.
 (Travelling Expenses, if any, £)

Committee's Minute Tuesday, December, 13th. 1881

Assigned B.S. 12 The boiler is subject to the boiler

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Clyde District Lloyd's Register Foundation Sub owners

(Insert Character precisely as in the Register Book.)

GLS146-0190

556486

I have the notations
 No. 12 & 13 recorded, subject to
 the British being preserved
~~in~~ in two months
 on account of their
 condition

18/12/59

© 2019

Lloyd's Register
Foundation