

Report of Survey for Repairs of Engines and Boilers.

No. *6004* (Received at London Office, *19th FEB. 83.*)
 No. in Reg. Book. *12.* Survey held at *Glasgow & Greenock* Date, first Survey *30.1.83.* Last Survey *5th Feb.* 188 *3.*

on the Machinery of the *Screw Steamer Queen* (Number of Visits *4*)

Tonnage, Gross *405.* Built at *Glasgow* When built *1854.*

Ditto, Net *284.* Owners *H. McIlwraith.* Port belonging to *Dundee*

Diameter of Cylinder *20"-36"* Engines made by *H. B. Thompson* When made

Length of Stroke *22 1/2"* Boilers made by When made

Pressure of Steam *65 lbs.* If Surveyed Afloat or in Dry Dock *At W. Hendersons Slip.* Classed *100 A 1.*

Registered Horse Power *58.* (State name of Dock.) *7.82.*

Last Survey No. Port *L.M.C. 1.80. B.S. 3.81.*

Particulars of Repairs and Examination *Periodical*

*Cylinders opened up and pistons examined.
 Top and bottom ends overhauled and examined.
 Propeller, tunnel and thrust shafts examined.
 Propeller and stern tube examined.
 All sea cocks and connections examined.
 Bilge suction pipe renewed.
 Key in cock connecting sea and bilge suction renewed.*

*Main and Donkey Boilers examined outside and in.
 Several patches put on in back of combustion Chamber.
 One screw stay renewed in combustion Chamber.
 Two new tubes put in.
 Four new fitted bolts put in bottom of shell joint
 in place of worn out rivets and 5/16" steel covering
 plate put on to save rivet heads.
 Examined Boiler under steam pressure everything tight.
 Steam trial of Engines everything satisfactory.*

General Observations, Opinion, and Recommendation:— *The above repairs are now completed and the machinery in good working condition and eligible in my opinion to be noted in Register Book* *L.M.C. 2.83.*

Entry or Registering Fee... £ : :
 Survey Fee (per Section 27.) ... £ *3* : *3* :
 Certificate (if required) ... £ : :
 Travelling Expenses, if any, £ *5/-*


received by me, *15/2/1883*

John Sanderson

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute *188*

Assigned *Def 2, 83*



GLS147-0329

6007 Jls

It is submitted that this vessel is
eligible to have the notification
Lm 6283 recorded

D.S.

19/2/83



© 2019

Lloyd's Register
Foundation