

Report of Survey for Repairs of Engines and Boilers.

No. 6093 (Received at London Office, Rec'd 7th MAY 1883.)

No. in Reg. Book. 955 Survey held at Glasgow Date, first Survey 20th April Last Survey 27th April 1883
on the Machinery of the Screw Steamer "State of Pennsylvania" (Number of Visits 3)
Tonnage, Gross 2472 Built at Glasgow When built 1873
Ditto, Net 1593 Owners The State Steam Ship Co. Ld. Port belonging to Glasgow
Diameter of Cylinder 46" 82" Engines made by The London & Glasgow Co. Ld. When made 1873
Length of Stroke 45" Boilers made by Do. When made 1873
Pressure of Steam 70 lbs If Surveyed Afloat or in Dry Dock Both - Govan Dock. (State name of Dock.)
Registered Horse Power 400 Classified 100A1
Last Survey No. Port L.M.C. 5-82.

Particulars of Repairs and Examination Annual Survey.

When this vessel was in Dry Dock the sea cocks & valves outer end of stern tube - Propeller & were all examined. Two of the Propeller blades somewhat badly corroded on the back near to the tips. These were well covered with cement & are not of importance. Main boilers opened out for survey & examined over all parts - safety valves taken asunder & thoroughly cleaned. In engine room the High & Low Pressure cylinders & slide valves, also the crank shaft, shafting, air circulating, Feed & Bilge Pumps & connections were all examined. The Forward crank shaft has been taken out & replaced by a new built one of steel made by Messrs Vickers of Sheffield.

General Observations, Opinion, and Recommendation:— The new Forward crank shaft has been well fitted in its place & the Engines & Boilers are now in good working condition. I would recommend that the notification L.M.C. 4-83 be made in the Register Book, & the vessel struck out of the limited period list on which it was placed owing to the condition of the crank shaft.

Entry or Registering Fee... £ : : Survey Fee (per Section 27.)... £ 2 : 2 : Certificate (if required) ... £ : :
received by me, 5/5 1883
Walter E. Rolson
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.
Glasgow
Committee's Minute 188
Assigned L.M.C. 4-83

Report is also sent on the condition of the ship, on the condition of the engines and boilers, and subsequent repairs and examinations, to be clearly stated.

Insert Character precisely as in the Register Book.

GLS148-0021

6093 gls

It is submitted that this vessel is
eligible to have the notification
of 2nd L 4193 recorded and be
removed from the limited list

D.F.

7/5/83



© 2019

Lloyd's Register
Foundation