

Report of Survey for Repairs, &c., of Engines & Boilers.

No. 6489

No. in Survey held at

Glasgow

(Received at London Office,

MONDAY 5 JAN 1885

Reg. Book.

595 on the Machinery of the

S. S. Amrapora

Date, first Survey Nov 28th

Last Survey Dec 1st 1884

(Number of Visits Two)

Tonnage, Gross 2464

Built at Greenwich

When built 1874 7th

Ditto, Net 1619

Owners British & Burmah Steam Nav Co Ltd

Port belonging to Glasgow

Diameter of Cylinder 45 x 78

Engines made by Greenwich Foundry Co

When made 1874

Length of Stroke 45

Boilers made by

When made 1883

Pressure of Steam 70 lb

If Surveyed Afloat or in Dry Dock Henderson Dock

Classed 100 A. 9-83

Registered Horse Power 300

Last Survey No.

Port

L.M.C. 9-83 + N.B. 83

Particulars of Repairs and Examination

Annual

(State clearly the cause of Repairs if any, and in detail, the nature and extent of Examinations and subsequent Repairs. Repairs due to other causes. State also the dates and initials of any letters respecting this case.

Repairs on account of Damage should be separated from

Main & donkey boilers of this vessel examined over all parts - also safety valves, pipes, connections &c. Side plates of donkey boiler somewhat wasted by corrosion & have been stiffened at this time by L iron riveted to plate between rows of stays. When vessel was in dock sea cocks, valves &c all overhauled. Two new blades fitted to propeller.

General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

On above examination the machinery of this vessel is now in good & safe working condition & in my opinion eligible to remain as classed in the Register Book with the additional notification B. S. 12-84.

Office or Registration Fee (per Section 27)

Survey Fee (per Section 28)

Special Damage Fee (per Section 28)

Certificate (if required)

Travelling Expenses (if chargeable)

received by me,

3/11 1885

Walter R. Brown
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute

Assigned

B. S. 12, A.

Glasgow

Lloyd's Register Foundation

It is submitted that this vessel is
eligible to have the notification
B.S. 12.84 recorded.

DP

5/1/85

