

Report of Survey for Repairs, &c., of Engines & Boilers.

4298

No. 4298
 No. in Survey held at Glasgow Date, first Survey 23rd Nov 1885 Last Survey June 28th 1886
 Reg. Book. 480 on the Machinery of the "S. S. Ethelbert" (Number of Visits 4)
 Tonnage, Gross 401 Built at Belfast When built 1881
 Ditto, Net 323 Owners Colvile Lowden & Coy Port belonging to Glasgow
 Diameter of Cylinders 22 & 40 Engines made by Muir & Houston When made 1881
 Length of Stroke 30" Boilers made by " " " When made 1881
 Pressure of Steam 80 lbs If Surveyed Afloat or in Dry Dock Afloat and on Glasgow Slip Classed 100 A.1
 Registered Horse Power 40 (State Name of Dock.) Helpinhaugh Slip 5/83
 Last Survey No. 40 Port + L.M.C. 3/81

Particulars of Repairs and Examination Completion of N.T. Survey (see Glasgow Report 1886)
 (State clearly the cause of Repairs if any, and in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

New propeller shaft fitted. New Safety valve springs fitted, pumps pipes & rods overhauled & cleaned, working parts of Engines examined.
Main boiler fitted with new tubes
Doukey boiler examined
Safety valves tested under steam the main boiler to 80 lbs working pressure & the Doukey boiler to 40 lbs.

It is submitted that this vessel is now eligible to have the 1.86 records, the boiler being subject to cleaning as per Rule M. 14/86

General Observations, Opinion, and Recommendation :--
 (State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)
The above repairs have been satisfactorily completed and the machinery is now eligible in my opinion to be noted in the Register Book + L.M.C. 1/86

Office or Registration Fee (per Sec. 27) £ : :
 Survey Fee (per Section 28) £ 2 2 -
 Special Damage Fee (per Section 28) £ : :
 *Certificate (if required) £ : :
 Travelling Expenses (if chargeable) £ : :
 Committee's Minute
 Assigned + L.M.C. 1.16

received by me. 29/11/86 188

James Mollison
 Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.
Clyde District

TUESDAY 2 FEB 1886

Lloyd's Register Foundation

GL151 - 0306

Form No. 9 - Transfer Ink - 19/2/85. (The Surveyors are requested not to write on or below the space for Committee's Minute.)

Insert in Register of Ship and Machinery precisely as in the Register Book.