

# REPORT of SURVEY for REPAIRS, &c.

No. 9298 Date of Writing Report 188 Port of Glasgow  
 No. in Reg. Book. 268 Survey held at Glasgow Date, First Survey 2<sup>nd</sup> July 8 Last Survey 23<sup>rd</sup> July 1889  
 on the Iron B.C. "Northbester" Master G. Gordon

TONNAGE:—  
 NET 527  
 GROSS 567  
 UNDER DK. 560  
 Built at Glasgow By whom L. Hill & Co When 1864-9  
 Owners J. & A. Roxburgh Port belonging to Glasgow  
 Owner's Address (if not already recorded in Appendix to Register Book.)  
 If Surveyed Afloat or in Dry Dock Dry Name of Dock Jovan Destined Voyage Transatlantic  
 Length of Poop ft.: of Forecastle ft.: of Raised Or. Deck ft.: Moulded Depth 18 ft. 0 ins.  
 (if these particulars are not yet recorded in the Register Book.)  
 Last Survey, No. 884 Port Glasgow  
 Classified S. S. Ship No. 3. 79  
 S. S. Ship No. 2. 87  
 Years assigned, if a Wood Ship. 3 ft. 0 ins. in Summer  
 10. 88. in Winter  
 Character in Register Book. A 1  
 (State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and Initials of any letters respecting this case.)

## REPAIRS, OR EXAMINATION AS PER RULE, FOR

The outside examined, scraped & repainted. The Rudder pintles rebushed. The plating in the strake below-deck being indented with anchor now doubled with plate 5-6 each side. The Bowport. Keel bits & planking in way of same being defective this decay now renewed of pitch & i.e. For strengthening frames in Forecastle slightly cracked two diag. plates fitted from Forecastle beams each side. For replacement of similar articles lost there has now been put on board.

Weight & Test  
 15-2-3 17-0-3-21  
 15 ft. Chain Cable 1 1/6 stud link - 55 lb. & 57 1/2 lb. test  
 Laid by S. Lewis  
 Retherton.  
 Laid by H. Linton  
 Retherton.  
 Weight & Test  
 15-1-0 17-1-0  
 1 1/6

A new set of square sails supplied for main mast.

No. of certificate of Anchor 24805  
 " " " Chain cable 18674

Part cargo in hold at time of survey.

PRESENT CONDITION OF THE		Boats	
Decks	Plating (Bottom) & Counter	Boats	Boats
Waterways	Breastworks or Rivets	Masts, Yards, &c.	Masts, Yards, &c.
Comings	Breasthooks and Stemson	Condition, how ascertained	Condition, how ascertained
Up'r Dk. Beams & Fastenings	Transoms, Pointers, & Crutches	Sails	Sails
Low'r Dk. Beams & Fastenings	Timbers of Frame at the opening	Anchors No. of	Anchors No. of
Planksheers	Ditto ditto at other places	Cables	Cables
Sheerstrakes	Keelsons	Hawsers & Warps	Hawsers & Warps
Topsides	Clamps & Shelves	Standing & Running Rigging	Standing & Running Rigging
Wales		Hatches	Hatches
Engine Room Skylights	Coal Bunker, Openings, Lids, &c.	Scuppers	Scuppers
		Cargo & Main Hatchways	Cargo & Main Hatchways

## General Observations, Opinion as to Class, Recommendation, &c.:

This vessel appears to be in good condition, in my opinion eligible to remain as classed & to have record of Survey Jls 7.89

Entry Fee (if chargeable) per Scale I., Sec. 27... £  
 Office Fee (if chargeable) per Scale II., Sec. 27... £  
 Survey Fee (per Section 28) £  
 Special on Damage, Fee (if any) per Sec. 28... £  
 \*Certificate (if required) to be sent as per minute £  
 Travelling Expenses (if chargeable) £  
 Second Surveyor's Fee (if any) £

Fees applied for,

188

Received by me,

188

Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute  
 Character assigned

FRIDAY 26 JULY 1889



Lloyd's Register  
 Foundation