

No. 11282

# REPORT of SURVEY for REPAIRS, &c.

TUES. 11 FEB 1892

Date of writing Report 18 When handed in at Local Office 18 Port of Glasgow

No. in Reg. Book 215 Survey held at Glasgow Date, First Survey 10th January 1892 Last Survey 29th January 1892  
on the Iron screw steamer "Lennox" Master Ward 91.91

TONNAGE: Built at Glasgow By whom A. Stephen & Sons When 1880  
GROSS 2051 Owners J. Harrick Port belonging to Leith  
UNDER DEK 1904  
NET 1327

Surveyed Afloat or in Dry Dock? Dry Dock Name of Dock Meadowside Destined Voyage China  
WB=Deba tons; f tons; uE&B tons; CellDB tons; FPT tons; APT tons; MT tons.

Last Survey, No. 10243 Port Glasgow  
Particulars of Classification (which must be inserted precisely as in Register Book & Supplements.)

CHARACTER, &c. for Special Survey. Date of last Survey and of Periodical Surveys.	Years Allowed now expired.	Machinery and Boiler Surveys (including date of N.B., if any).
100A.1		T.L.M.C. 4.88
10.90		B.S. 11.90
S.S. Liv No. 3.4.88		

Society's Freeboard (if assigned) as painted on Ship and now verified 5 5 ft 5 1/2 ins.

REPAIRS, OR EXAMINATION AS PER RULE, FOR *Special Survey No. 1.*

*This vessel has been placed in dry dock the bottom cleaned and coated; holds, peaks and bunkers cleared, all close ceiling removed from top of tanks of cellular D.B. and the tank tops cleaned and coated with tar and cement; the tanks retested by water pressure. Examination made inside of tanks, the tank under engines and Boilers chipped, cleaned, and recoated with cement wash, examination made in bunker spaces and the iron work in same chipped cleaned and recoated. Examination made in peaks and the fore peak cleaned and recoated with cement wash. Masts, Spars and rigging examined, chain cables ranged.*

*Repair - beamings of coaling hatchway on starboard side fitted with doubling plates*

MARY OF DAMAGE REPAIRS: -  Plates, Fair'd or Repaired;  Frames, ditto.  Plates, Renewed;  Frames, ditto. Other Repairs: *coaling hatchway*

PRESENT CONDITION OF THE	Transoms, Pointers, & Crutches	Copper, or Y.M. (State if on Felt.) When put on, Month Year	Hatches
<i>good</i>	<i>good</i>	<input checked="" type="checkbox"/>	<i>good</i>
Waterways	Timbers of Frame at the openings	When put on, Month Year	Boats
Beamings	Ditto ditto at other places		Masts, Yards, &c.
Starboard Dk. Beams & Fastenings	Keelsons	Rudder <i>good</i>	Condition, how ascertained <i>by exam<sup>n</sup></i>
Starboard Dk. Beams & Fastenings	Clamps, Shelves & Stringers	Windlass & Capstan	Sails <i>good</i>
Plating	Footing	Pumps	Anchors No. of <i>3B-15-2K</i>
Planking	Ceiling	Engine Room Skylights	Cables, length <i>270</i> size
Bronzeails or Rivets	Cement or Asphalt (State which)	Coal Bunker, Open'gs, Lids, &c.	(State if now ranged <i>ranged</i> )
Breasthooks & Stemson	Tanks (State if now tested)	Scuppers	Hawsers & Warps <i>good</i>
	Caulking of Bot'm, D'k, & Wat'r'ys	Cargo & Main H'tch'ys	Standing & Running Rigging

General Observations, Opinion as to Class, Recommendation, &c.

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and pEND91, &c."

*This vessel is in a good and efficient condition and in my opinion eligible to remain as classed and to have record of survey 2.92 and the notations of S.S. Gls. No. 1.92*

Office Fee (if chargeable) per Scale II, Sec. 27 £ : : Fees applied for, 6/2/92

Survey Fee (per Section 28) £ 4 : 10 : Received by me, 9/2/92

Special Damage or Repair Fee (if any) (per Sec. 28.) £ : :  
Travelling Expenses (if chargeable) £ : :  
Second Surveyor's Fee (if any) £ " : 10 :  
\*Is Certificate now required? *yes*

Committee's Minute TUES. 16 FEB 1892

Character assigned *100A.1 + L.M.C. 2.92 ss. No 1-92*

No. 1

