

REPORT of SURVEY for REPAIRS, &c.

Date of writing Report *14th Nov 92* When handed in at Local Office *15th Nov 92* Port of *Glasgow*
 No. in Reg. Book *165* Survey held at *Ardrrossan* Date First Survey *5th Oct 1892* Last Survey *4th Nov 1892*
 on the *Iron Ship Candakar* Master *W. Richards*

TONNAGE:-
 GROSS *1495*
 UNDER DK. *1373*
 NET *1357*
 Built at *Belfast* By whom *Harland & Wolff* When *1866* MONTH *5*
 Owners *S. Goldberg & Sons* Port belonging to *Swansea*
 Owners' Address
 (if not already recorded in Appendix to Register Book.)
 Surveyed Afloat or in Dry Dock? *Afloat* Name of Dock *Eglinton Dock* Destined Voyage *Cardiff*

W'B=DbA tons; f tons; uE&B tons; CellDB tons; }
 FPT tons; APT tons; MT tons.
 Last Survey, No. *5365* Port *Buo*

CHARACTER.	Years assigned	Machinery and Boiler Surveys (including date of N.B., if any).
*A.1	8.91	
S.S. Bro. No 3	8.91	

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).
 Society's Freeboard (if assigned) as painted on Ship and now verified

REPAIRS, OR EXAMINATION AS PER RULE, FOR *Damage through Stress of Weather.*

One bulwark plate on Port side, and four wash ports plates renewed; fore end of after cabin repaired; gangway platform and twenty six lengths of yellow pine deck to top of Poop renewed; teak ladder on Starboard side renewed and ladder on port side repaired; Port life boat repaired; one boats' skid renewed; cast iron stand for Capstan bars made good; Iron rails round monkey poop and Forecastle repaired; scarp of main rail refastened and twelve bays of bulwark paneling on Port side renewed; fore end of Fore deck house repaired; Fore topmast, upper topsail yard and fore topmast rigging and ten sheave blocks renewed; mizen lower topsail yard renewed. The Forecastle deck, which was found defective, was promised by Owners representative to be made good at port of loading Cardiff to which port the vessel proceeded on 11th inst in tow of tug, the following sails and manila hawser including main top gallant sail, lower main sail, upper fore topsail; lower mizen topsail and trinity fathoms of 4 1/2 manila hawser have also to be examined. The Cardiff Surveyors have been advised.

SUMMARY OF DAMAGE REPAIRS: — Plates, Faired or Repaired; Frames, ditto. *Plates, Renewed;* Frames, ditto. Other Repairs *as stated above*

PRESENT CONDITION OF THE		Paint		Hatches	
Decks <i>Good</i>	Transoms, Pointers, & Crutches <i>Good</i>	Copper, or Y.M. (State if on Felt.)	When put on, Month	Year	Boats <i>Good</i>
Waterways	Ditto ditto at other places	Rudder	<i>Good</i>		Masts, Yards, &c.
Coamings	Keelsons	Windlass & Capstan			Condition, how ascertained <i>By examination</i>
Up'r Dk. Beams & Fastenings	Clamps, Shelves & Stringers	Pumps			Sails <i>Part new</i>
Low'r Dk. Beams & Fastenings	Salting	Engine Room Skylights			Anchors No. of <i>36, 15, 2 1/2</i>
Plating	Ceiling	Coal Bunker, Open'gs, Lids, &c.			Cables, length size (State if now ranged) <i>Not ranged</i>
Planking	Cement or Asphalt (State which.)	Scuppers			Hawsers & Warps <i>Good</i>
Tread-boards or Rivets	Tanks (State if now tested.)	Cargo & Main H'tchw'ys			Standing & Running Rigging
Breasthooks & Stemson	Caulking of Bot'm, D'k, & Wat'rw'ys				

General Observations, Opinion as to Class, Recommendation, &c.:

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—".....to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and pEND91, &c."

This vessel is now in good and efficient condition, with the exception of Forecastle deck above referred to, and eligible to remain as classed when this deck is renewed and sails and hawser have been examined

Office Fee (if chargeable) per Scale II., Sec. 27	Survey Fee (per Section 28)	Special Damage or Repair Fee (if any) (per Sec. 29)	Travelling Expenses (if chargeable)	Second Surveyor's Fee (if any)	*Is Certificate now required?
£	£ 3 : 13 : 6	£	£ 1 : 5 : 0	£	

Fees applied for, *2/11/92*
 Received by me, *4/11/92*

Charles Edwards
 Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute
 Character assigned *Deferred for Write off Rpt. w/ Eff. compl. of repairs 18/11/92*

