

No. 12261

## REPORT of SURVEY for REPAIRS, &amp;c.

Date of writing Report 15 When handed in at Local Office 15

Port of Glasgow

No. in  
Reg. Book.

Survey held at

Date, First Survey

11 May 1893

Last Survey 2 June 1893

(No. of Visits)

Master Sergeant

TONNAGE:-

GROSS 1139

UNDER DK. 984

NET 1092

Built at

Glasgow

By whom

A. Stephen &amp; Co.

When

1876

Owners' Address

(If not already recorded in Appendix to Register Book.)

Surveyed Afloat or in Dry Dock?

Afloat

Name of Dock

Kingston Dock

Destined Voyage

Dunedin

WB= DBa

tons; 1

tons; uE&amp;B

tons; Cell DB

tons; FPT

tons; APT

tons; MT

tons.

Last Survey, No. 54290

Port London

Particulars of Classification (which must be inserted precisely as in Register Book &amp; Supplements).

CHARACTER. For Special Survey. Date of last Survey and of Periodical Surveys.

100A1

2.92

S.S. Helen N° 3 11.88

Society's Freeboard (if assigned) as painted on Ship and now verified 3 ft. 9 ins.

(Periodical Surveys, when held, must be reported in detail and serially in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors or Chains is reported, the particulars of weight or size and test of the articles should be clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment Letter, if any. State also the dates and initials of any letters respecting this case.)

REPAIRS, OR EXAMINATION AS PER RULE, FOR Completion of Special Survey N° 1 see London Report N° 54290

Holds and peaks cleared, the timber hatches and one strake of ceiling removed fore and aft on each side of vessel. Examination made in holds & peaks of the frames, plating, keelsons, stringers, cement &c and found to be in good condition. The decks, windlass, pumps & bulwarks examined. Further examination has been made of the masts and spars by removal of the wedges, and examining the fore upper topsail yard and the iron main lower topsail yard on deck. The removal of the bowsprit wedges was deepened with as the bowsprit plating is doubled in way of wedging. Repairs - Spanker boom and gaff renewed, new main topmast. main upper topsail yard renewed, the iron lower main topsail yard has been repaired by fitting a doubling plate in way of indent, new wedges fitted to the fore upper topsail yard. Margin top to shackle and end link repaired.

SUMMARY OF DAMAGE REPAIRS: - Plates, Fair'd or Repaired: - Frames, ditto. - Plates, Renewed: - Frames, ditto. Other Repairs.

PRESENT CONDITION OF THE

|                              |      |                                   |      |                                 |          |                            |                   |
|------------------------------|------|-----------------------------------|------|---------------------------------|----------|----------------------------|-------------------|
| Decks                        | good | Transoms, Pointers, & Crutches    | good | Copper, or Y.M.                 | good     | Hatches                    | good              |
| Waterways                    | "    | Timbers of Frame at the openings  | "    | (State if on Felt.)             | "        | Boats                      | "                 |
| Coamings                     | "    | Ditto ditto at other places       | "    | When put on, Month              | Year     | Masts, Yards, &c.          | "                 |
| Upper Dk. Beams & Fastenings | "    | Keelsons                          | "    | Rudder                          | part new | Condition, how ascertained | by exam.          |
| Lower Dk. Beams & Fastenings | "    | Clamps, Shells & Stringers        | "    | Windlass & Capstan              | good     | Sails                      | good              |
| Plating                      | "    | Siding                            | "    | Pumps                           | by exam. | Anchors No. of             | 38-15-25          |
| Painting                     | "    | Ceiling                           | "    | Engine Room Skylights           | "        | Cables, length             | part new          |
| Keels or Rivets              | "    | Cement or Asphalt                 | "    | Coal Bunker, Open'gs, Lids, &c. | "        | (State if now ranged)      | no                |
| Hooks & Stems                | "    | Tanks                             | "    | Scuppers                        | "        | Hawsers & Warps            | good & sufficient |
|                              |      | Caulking of Bot'm, Dk. & Wat'r'ys | "    | Cargo & Main H'tch'ys           | "        | Standing & Running Rigging | good              |

General Observations, Opinion as to Class, Recommendation, &amp;c.:-

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and ptND91, &c."

This vessel is in a good and efficient condition and in our opinion eligible to remain as classed and to have record of survey 6.93 and the notations of S.S. fls. N° 1-93

|  |     |                   |
|--|-----|-------------------|
| Office Fee (if chargeable) per Scale II., Sec. 27    | £   | Fees applied for, |
| Survey Fee (per Section 25)                          | £ 4 | 2/6/ 1893         |
| Special Damage or Repair Fee (if any) (per Sec. 28.) | £   | Received by me,   |
| Travelling Expenses (if chargeable)                  | £   | 5/6/ 1893         |
| Second Surveyor's Fee (if any)                       | £   |                   |

\* Certificate required? Yes

Committee's Minute

Character assigned

LLOYD'S REGISTER WRITTEN

FRI 9 JUN 1893

100A1

ss No. 1-93

© 2019

Lloyd's Register Foundation

GLS 1678-0080

In a Report also per the Machinery of the Ship? If not, state whether, and when, one will be sent?

N.B.—All alterations in the existing records should be indelible.

Form No. 2 for Repairs, 200,000, 24/10/91.—Transfer Ink. (The Surveyors are requested not to write on, or below the space for Committee's Minute.)