

14435. *egm*

Case plate of Tank Top on port side in way of boilers renewed the
 Tank top plating under boilers fitted with 3/4" doubling plates, these
 plates extending from middle line strake to strake at margin
 under boilers and at ends. The intercostal floor plates between
 No. 1 & No. 2 longitudinals and between No. 2 & No. 3 longitudinals stiffened
 by fitting double vertical angles at side of man holes to seven floors
 in way of boilers, the longitudinals at this part of vessel
 fitted with doubling plates at lower part and vertical angles
 the tank tested after repairs and coated with thick cement on
 top. The bulwork plating at ends of Bridge House on both sides of
 vessel doubled.

H. B.
C. J. B.

N.B.—If this Report is copied by Copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or cause it to show through to the other side.

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.



© 2019

Lloyd's Register
 Foundation