

7978  
№ 368

S.S. "DUNKELD"

R. Napier & Sons,  
Glasgow.

Midship Section

Glasgow Report No 4731

To Class 100 A. Two Decked Steamer

Scale  $\frac{1}{2}$  inch = 1 foot.

Rec 8/5/78

Lloyd's Dimensions  
Length --- 238.64  
Breadth --- 32.0 moulded  
Depth --- 20.7 tip of beam at centre

Numerals  
 $\frac{1}{2}$  Breadth --- 16' 0"  
 Depth --- 20' 4"  
 $\frac{1}{2}$  Girth --- 32' 6"  
1<sup>st</sup> Numeral = 69' 3"  
 2<sup>nd</sup> = 69' 3" + 238' 6" = 308' 9"

Frames  $4\frac{1}{2} \times 3 \times \frac{1}{16}$  for  $\frac{3}{8}$   $4\frac{1}{2} \times 3 \times \frac{1}{16}$  for  $\frac{1}{4}$  aft Spaced 23 inches  
Reverse Frames  $3 \times 3 \times \frac{1}{16}$  to Tween deck Stringer Angle iron  
and Upper Deck Alternately

Double from Bilge to Bilge in Machinery Space  
Floors  $21 \times \frac{9}{16}$  to  $\frac{7}{16}$  and  $\frac{1}{16}$  in Machinery Space

Bulkheads  $\frac{5}{16}$ " &  $\frac{7}{16}$ " Angles  $3 \times 3 \times \frac{1}{16}$

Rudder Stock  $5\frac{3}{4}$  dia at head & 3" at keel

See plate 12,  $\frac{7}{16}$  to  $\frac{9}{16}$

proportions  
Under 8 Breadths (J. 45)  
Under 12 Depths (H. 53)

Equipment Numeral if flush Decker.  
16539

3 Boxer Anchors 60 lbwt (Collective) ex Stock  
1 Stream — " — 9' — — — — incl " —  
1 Hedge — " — 4 $\frac{1}{2}$ ' — — — — " —  
1 Hedge — " — 2 $\frac{1}{4}$ ' — — — — " —  
240 Fathoms 1 $\frac{8}{10}$ " Steel Chain Cable  
95' — " — 1 $\frac{5}{10}$ " Stream Chain  
90' " 10 $\frac{1}{2}$ " — 97 5 $\frac{1}{2}$ " Hawse

[illegible]

J.F.J.  
11/4/8

GLS187-0119