

S.S. "Jose Perez"
Glasgow Report No 5009

"Midship Section"

S.S. No. 7

Scale 1/2 inch to the foot.

Section in way of Bull-roop.
4 1/2" x 3" x 5/16" 2 1/2" 16" x 5/16" 3" x 3" x 5/16"

Principal Dimensions

Length from Stem to Post	164' 11"
Breadth moulded	24' 0"
Depth	13' 10"
Half girth of Midship Section	23' 8"
Camber on beams	6 1/2"
Half breadth	12' 0"
Depth	14' 37"
Half girth	23' 66"
No 5003 x 164.9 =	8249.94
Breadth to Length	6.87
Depth	11.57
Equipment No 8249 + 824 =	9073.

Frames for 1/2 length	3' x 3' x 5/16"
Reverse frames	2 1/2' x 2 1/2' x 5/16"
Floor plate for 1/2 length	1' 2' x 6' 1/6" x 7' 1/6" in engine boiler room.
Reverse plate	1' 2' x 5/16"
Pillars in hold	2 1/2" dia.
Bulkheads	1/4"
Kid	7 1/2' x 1 7/8"
Stem	7 1/2' x 1 7/8"
Stem-post	6 1/2' x 3 3/4"
Quadder	4 1/4' x 2 1/2"

Equipment

1 Borer	4' 10" Cnts
1	10" - -
1	4' 10" - -
1 Stream	3 3/4"
1 Keel	2 1/4' 1 1/2' 3/4"
195 Pals	1 1/8" Chain cable
60	1 1/6" Stream
75	8 1/2" Hawser
90	6 1/2"

R. CHAMBERS, JUN.
SHIPBUILDER,
WOODYARD, DUMBARTON

15/8/79



Lloyd's Register
Foundation

GLS188-0067