

Midship Section
No. 251

S.S. "Prins Alexander"
Glasgow Report No. 5574

100 A. 1 Spar deck brass
36.7
19.4 * 38.8
23.3
79.4 frames
34.8 length in rule
2763.2 Plating to be
26,400

Proportions 8.9 Bunch
14.9 Depth

1/16 for 174 ft.
1/16 main 43 ft. and
fore end, aft end 9/16

all ft.

or sheershafts 15/16 tapered to 1/16
and strakes below 15/16 to 9/16
without doubling as per rule.

11/16 for 174 ft.
10/16 main 43 ft.
9/16 at ends.

12/16 for 174 ft.
11/16 main 43 ft.
9/16 at ends.

10/16 for 174 ft.
9/16 main 43 ft.
7/16 at ends.

12/16 for 174 ft.
11/16 main 43 ft.
9/16 at ends.

Riveting. All bulks of stringers and tie plates
for 174 ft amidships to be rivetted and
to have built shapes 1/16 thicker for 260 ft
Bulks of upper deck sheershafts for 210 ft
lower deck sheershafts and one ridge shaft
for 174 ft to be rivetted.
All built shapes of shell plating 1/16
thicker than plates they connect for
260 ft amidships.

Doubled for 260 ft.
with 1/16 x 9/16



Scale 1/2 inch to one foot