



Lk: 5 Lls.
12/3/83.

B.M. "Noddleburn"

Glasgow Report No. 6142

RECEIVED 9th MAR. 88.



Masts & Yards No. 35 (Barque)
(Mast Palace)

7th March 1883

Fore Mast Length extreme 116. 2"

Length from Haul to lower mast Head 82. 8" Mast Head 14. 0

" " Lower mast Hounds to topmast Head 47. 6

Dia. Partners 29 Haul 21 Hounds 22½ Cap 19" Topmast Hounds 14 Cap 11½
Thick^s 5/16 6/16 6/16 6/16 6/16 4/16 4/16

Main Mast Length extreme 115. 4"

Length from Haul to lower mast Head 81-10" Mast Head 14. 0

" " Lower mast Hounds to topmast Head 47. 6

Dimensions & Thicknesses same as Fore Mast

Mizen Mast Length extreme 130. 6

Length from Haul to lower mast Head 82. 0

" " Lower mast Head to topmast Head 29. 0

" " topmast Head to topgallant mast Head 19. 6

Dia. Partners 23½ Haul 17½ Hounds 18½ Cap 15½ Topmast Head 12" Topgallant Head 7
Thick^s 6/16 5/16 5/16 5/16 5/16 4/16 3/16

Bowport Length outside of Bed 21. 0"

Dimensions Bed 27 Haul 22 Cap 17½

Thick^s 7/16 6/16 6/16

Fore & Main Lower Yards Length extreme 77. 0

Dia: - Centre 19, 1st Quat. 18½, 2nd Quat. 17½, 3rd Quat. 14½, Ends 9½

Thick^s 6/8 5/8 5/8 4/8 3/8

Fore & Main Lower Topsail Yards Length extreme 65. 9"

Dia: Centre 16, 1st Quat. 15½, 2nd Quat. 14½, 3rd Quat. 12, Ends 8

Thick^s 5/8 5/8 5/8 4/8 3/8

Fore & Main Upper Topsail Yards Length extreme 62. 8"

Dia. Centre 15, 1st Quat. 14½, 2nd Quat. 13½, 3rd Quat. 11½, Ends 7½

Thick^s 4/8 4/8 4/8 3/8 3/8


Bowport to have 3 Angles 3½" x 3" x 6/8

Mast & Bowport 3 plates in the round. Yards 2 plates in the round

Topmasts 2 plates in the round.

Bargue No 38
Marto & Yards

7/3/83





© 2021

Lloyd's Register
Foundation